

December 5, 2025

**Subject: ITB # 26073-B: FY26 Resurfacing Project**  
**Addendum #1**

Gentlemen/Ladies:

Below, please find responses to questions, clarification, or additional information for the above referenced ITB. You will need to consider this information when preparing your bid.

1. **Can the County please provide the start and end points for each road? Several of the roads just state lengths, instead of starting and ending points.**
  - a. Flat Creek Trail – SR 54 to Tyrone Road
  - b. Bethea Road – SR 314 to Longview Road
  - c. Bohannon Road – Fulton County Line to Fulton County Line
  - d. Kirkley Road – SR 74 to Bohannon Road
  - e. Lester Road – SR 54 to Fayetteville City Limits and Fayetteville City Limits to Ebenezer Church Road
  - f. Tyrone Road – SR 54 to Town of Tyrone City Limits
  - g. Kenwood Business Park (Carnes Drive, Cecil Court, Ethan Drive, Etowah Trace, Marksmen Court, Tober Trail and Walter Way) entrances off of SR 85 and Old Road.
2. **Could you provide start/end points for the roads listed? See question #1.**
3. **Will a MTV(Shuttle Buggy) be required on any of the roads in this project? An MTV will be required on all roads except the roads within the Kenwood Business Park (Carnes Drive, Cecil Court, Ethan Drive, Etowah Trace, Marksmen Court, Tober Trail and Walter Way).**
4. **Are we required to use post mounted or tripod signs? The contractor will have the option to use either method.**
5. **Could you clarify what the “grading per mile” consist of? What does the 5.61 miles define on this project? The miles do not match what is required for shoulder building as stated on the road list. Grading should be 14.72 miles to match the road list. Please use the attached updated Price Sheet (Attachment 1).**
6. **Are temporary warning signs okay to use for this project in place of post mounted signs? See question #4**

7. On the roads that are getting an FDR treatment, will wet curing be okay or will prime and sand be required? As long as it meets GDOT specifications wet curing will be acceptable.
8. Could you give us the beginning and end points for all the roads on this contract? See question #1.
9. Will the county want to edge mill or full width mill the roads in this contract? Each road estimated milling needs are estimated under Section T of the bid document.
10. Can road widths please be provided?
  - a. Flat Creek Trail – Estimated 25'
  - b. Bethea Road – Estimated 20'
  - c. Bohannon Road – Estimated 20'
  - d. Kirkley Road – Estimated 22' & 20'
  - e. Lester Road – SR 54 to Fayetteville City Limits and Fayetteville City Limits to Ebenezer Church Road. Section #1 Varies 95' to 36', Section #2 20'
  - f. Tyrone Road – Estimated 24'
  - g. Kenwood Business Park (Carnes Drive, Cecil Court, Ethan Drive, Etowah Trace, Marksmen Court, Tober Trail and Walter Way) entrances off of SR 85 and Old Road. Estimated 24'

Received by (Name): \_\_\_\_\_ Company \_\_\_\_\_

Note: If this addendum is not returned to the Fayette County Purchasing Department or if it is returned not signed, responding individuals, companies or other organizations will still be responsible for the requirements of this addendum and the specifications or changes herein.

The opening date for this ITB has not changed. **The opening time and date are 3:00p.m., Wednesday, December 17, 2025.** Bids must be received by the Purchasing Department at the address above, Suite 204, at or before the opening date and time.

The deadline for inquiries has passed, so the Purchasing Department will not be able to accept any additional questions after this time.

If you have questions, please contact Sherry Poorman, Contract Administrator at (770) 305-5314 fax (770) 719-5544 or email at [spoorman@fayettecountyga.gov](mailto:spoorman@fayettecountyga.gov).

Sincerely,



Ted L. Burgess  
Director of Purchasing



ITB #26073-B FY26 Resurfacing Project

PRICE SHEET

3:00p.m., Wednesday, December 17, 2025

ITEM NO.	DESCRIPTION	UNIT	QTY	Unit Cost	Total Cost
150-1000	Traffic Control	LS	1		0
210-0200	Grading per Mile	LM	14.72		0
315-1010	CSRB	SY	19463		0
315-1000	Cement	TN	742		0
402-3130	12.5mm, SP GP 2, Incl Bitum Matl & H Lime	TN	10031		0
402-4510	12.5mm SP, GP 2, Incl Polymer Modified Bitum Matl, & H Lime	TN	5663		0
402-3190	19mm SP GP 1 or 2, Incl Bitum Material & H Lime	TN	3791		0
402-1802	19mm Patching	TN	2079		0
415-5000	Asphalt Concrete Open Graded Interlayer, GP 2 Only, Incl Bitum Matl & H Lime	TN	4818		0
407-0010	Crack Sealing	LM	6.55		0
413-0750	Bitum Tack Coat	GAL	23765		0
432-5010	Mill Asph Conc Pvmt, Varible Depth	SY	123144		0
653-1502	5" Yellow Thermoplastic Striping	LM	15.96		0
653-1501	5" White Thermoplastic Striping	LM	16.46		0
653-3501	5" White Skip Thermoplastic	GLF	4962		0
653-0120	Arrows, TP 2	EA	24		0
653-6006	Thermoplastic Traf Striping White	SY	296		0
653	Thermoplastic Traf Striping Yellow	SY	269		0
653-1704	24" Stop Bars	LF	312		0
	Thermoplastic Word ONLY	EA	12		0
654-1001	RPMS (Type 1, 2 & 3)	EA	2041		0
700-6910	Permanent Grassing	AC	3.4		0
TOTAL BID PRICE					0