

Types of Inspections: Pools

- **Niche Pool** Electrical conduit and light-niche forming shells installed, bonded and stubbed out. Apply listed potting compound to the light-niche forming shells and junction boxes
- **Grounding Pool** Basket, ladders, handrails, metal and all equipotential bonding complete
- **Ditch Cover-Up Electrical** Trenches excavated and underground conduit in place
- **Ditch Cover-Up Gasline** Trenches excavated piping and tracer wire in place (if required)
- **Gasline** Pressure Test
- **Rough Electrical** Rough wiring complete and trenches covered
- **Plumbing Pool** Underground lines covered. Main drains as required. Pressure test (15# min. 30 minutes) is required – **(Commercial only)**
- **Mechanical Pool** Installation of heater equipment complete and ready for startup
- **Final Electrical** Grounding of motor; location of GFCI outlets; all electrical complete
- **Clear Holds** **All re-inspections fees and holds must be cleared before scheduling Pool Final Inspection.**
- **Final Pool** Must Request A.M. or P.M. inspections – Access barriers complete; alarms installed; equipment installed; all plumbing, gas lines and heaters operating; all above inspections complete.