



Fayette County, Georgia Permits & Inspections Department Residential Single Family Dwelling

"Rough Heat & Final Heat"
"The Most Common Code Violations"

Rough Heat

- Ensure all vents are terminated properly.
- Ensure the dryer vent is 3' away from any interior opening.
- Mechanical vents must be installed per Manufacturers installation Instructions / code.
- Install AHUs and fully support per Manufacturers Installation Instructions or code.
- · Fireplaces, flues, and gaslines must be installed.
- · Install and support all duct work per code.
- Duct work must not be crushed, or damaged.
- Seal ducts per code at joints, registers, and plenums.
- Ducts in garages must be hard duct or separated from the garage by fire-resistant construction.
- · Ducts must not be installed in fireplace chases.
- Bath fans must be installed per Manufacturers Installation Instructions / code, be properly vented to the exterior with the duct taped to the fan.
- Maintain clearances around jall appliances and flues per code.
- AC linesets must be properly installed with no damage to the insulation on the lineset.

Fayette County, Georgia "Where Quality is a Lifestyle"...







Final Heat

- · Secure and seal all duct and flue terminations.
- Bath fan termination must have a wire screen per code.
- Dryer termination must not have a wire screen (fire hazard).
- Ensure the range / cooktop is installed per Manufacturer's Installation Instructions.
- Kitchen cabinets must meet the clearances listed in the Manufacturer's Installation Instructions.
- Provide Manufacturers Installation Instructions for cooktop and range hood.
- Fireplace must be complete, clean and ready for startup.
- Bath fans must be operational.
- Vent covers must be installed and flush with the ceiling, floor or wall as applicable.
- Exterior AC units must be properly installed, level and with the correct breaker sizes installed in the electrical panel.
- Locking Access Port covers must be installed on Freon ports.
- Provide a complete energy code compliance certificate with blower door test and duct test results.
- Blower door test under 5 require outdoor air to be brought into structure at proper intervals to code.
- AHUs must be operational with plenums sealed to units per code.
- AHU drains must be properly installed with pan and / or float switch to code.
- CHECK ALL ITEMS LISTED ABOVE BEFORE CALLING FOR AN INSPECTION.

