FAYETTE COUNTY DOGWOOD TRAIL CULVERT REPLACEMENT PROJECT PROJECT NUMBER 17SAH



INDEX OF DRAWINGS

GENERAL

LEGEND AND ABBREVIATIONS

GRADING AND DRAINAGE PLAN

EROSION CONTROL PLAN
CONSTRUCTION DETAILS

CONSTRUCTION DETAILS

NPDES NOTES
NPDES NOTES

NPDES CHECKLIST

EROSION CONTROL DETAILS

GRADING AND DRAINAGE PROFILE

EXISTING CONDITIONS

DEMOLITION PLAN

SITE PLAN

COVER SHEET

Sheet No. Title

C-504

1899 POWERS FERRY ROAD SE, SUITE 400 ATLANTA, GEORGIA 30339

TEL: (770) 850-0949 FAX: (770) 850-0950



www.tetratech.com

PROJECT LO	CATIO	ľ
------------	-------	---

315 DOGWOOD TRAIL TYRONE, GA 30290 **CLIENT INFORMATION:**

FAYETTE COUNTY 140 STONEWALL AVE W, SUITE 203

FAYETTEVILLE, GA 30214

Tt PROJECT No.: CL

200-01297-18005

CLIENT PROJECT No.:

PROJECT DESCRIPTION / NOTES:


REFERENCE DATUM: NAD83 GEORGIA STATE PLANE, WEST ZONE, US FOOT

THE PROJECT SHALL CONSIST OF THE DEMOLITION OF THE EXISTING CMP CULVERT UNDER DOGWOOD TRAIL AND THE INSTALLATION OF 80 LINEAR FEET OF 48'X14' CONCRETE BOTTOMLESS ARCH CULVERT ALONG WITH THE RELOCATION OF THE EXISTING UTILITIES IN THE AREA.


ISSUED:

ISSUED FOR CONSTRUCTION - 03/08/19

VICINITY MAP:










NOT TO SCALE

PIPING LEG	BEND															
		FLAN	IGED			MECHANI	CAL JOINT			GROOV	E JOINT			SOLVE	NT WELD	
FITTING/ APPURTENANCE	SINGL	E-LINE	DOUBL	E-LINE	SINGL	E-LINE	DOUB	LE-LINE	SINGL	E-LINE	DOUBI	_E-LINE	SINGL	_E-LINE	DOUB	BLE-LINE
	EXISTING	PROPOSED	EXISTING	PROPOSED	EXISTING	PROPOSED	EXISTING	PROPOSED	EXISTING	PROPOSED	EXISTING	PROPOSED	EXISTING	PROPOSED	EXISTING	PROPOSED
BEND	+	+			+	屯				+			+	+		
TEE	+	+			1) + (+	小士(+				++			+	++-		
WYE					1)—(-	1)X		4 4		X						
REDUCER						⊣> ←				- >-			>	→> —		
CAP/ BLIND FLANGE					N/A	N/A	N/A	N/A		—	2	—				
PLUG	N/A	N/A	N/A	N/A	——(— (N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
BUTTERFLY VALVE		-1111-			-)+(-	⊣)+(⊢				—II			+	─ + -	21	-=+=
BALL VALVE		-1831-			N/A	N/A	N/A	N/A		-! ⊠ ! -			-181-	-184-		
CHECK VALVE					N/A	N/A	N/A	N/A		11				→		
GATE VALVE						→ ×⊢				→						
PLUG VALVE					-					- 				─ ₩		-5463-
AUTOMATIC CONTROL VALVE					N/A	N/A	N/A	N/A		→ \$						
PINCH VALVE					N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A				







ETTE COUNTY

O 03/08/19 ISSUED FOR CONSTRUCTION

CULVERT REPLACEMENT

SEND AND

EVIATIONS

U

GSWCC LEVEL II

CERT. # 0000073529

Project No.: 200-01297-18005

Designed By: CG

Drawn By: HA

Checked By: DL

LEGI BBR 2. THE ORDER OF MAJOR LAND DISTURBING ACTIVITIES IS INDICATED IN THE ACTIVITY SCHEDULE LOCATED ON SHEET C-503.

3. THE TOTAL AND DISTURBED ACREAGE FOR THE PROJECT IS 1.3 ACRES.

4. THE CULVERT REPLACEMENT PROJECT LOCATION IS: 33.45419° -84.56656°

FAYETTE COUNTY WATER SYSTEM NOTES

1. FAYETTE COUNTY WATER SYSTEM SPECIFICATIONS AND DETAILS SHALL GOVERN ALL WATER MAIN CONSTRUCTION.

2. ALL MATERIALS AND INSTALLATION SHALL BE IN ACCORDANCE WITH FAYETTE COUNTY WATER SYSTEM AND AWWA STANDARDS AND SPECIFICATIONS.

3. DUCTILE IRON PIPE (D.I.P.) SHALL BE MINIMUM PRESSURE CLASS 300 CEMENT MORTAR LINED, PER ANSI C151/A21.51. ALL FITTINGS SHALL BE MECHANICAL JOINT DUCTILE IRON PER ANSI A21.10 OR A21.53. ALL SERVICE PIPING SHALL BE COPPER.

4. PROVIDE THRUST RESTRAINT (THRUST BLOCKS OR RESTRAINED JOINTS) AT ALL BENDS, TEES, CROSSES AND END OF LINES. (EOL) SIDE FORMS SHALL BE USED TO PREVENT ENCASEMENT OF BOLTS. SERVICE TAPS SHALL NOT BE LOCATED BENEATH PAVEMENT.

5. MAINTAIN 24" MINIMUM CLEARANCE BETWEEN WATERLINE AND OTHER STRUCTURES.

6. CONTRACTOR SHALL MAINTAIN A MINIMUM OF 4' OVER ALL WATER LINES.

7. CONTRACTOR SHALL FLAG WATER LINE AND SERVICE LOCATIONS TO PREVENT DAMAGE BY OTHER UTILITY CONTRACTORS.

8. PROPER COMPACTION IS REQUIRED THROUGHOUT THE PROJECT. (95% PERVIOUS, 98% IMPERVIOUS)

9. UNSUITABLE SOIL MATERIALS SHALL BE REPLACED WITH SUITABLE MATERIALS.

10.NEW WATER LINE SHALL BE PRESSURE TESTED FOR 2 HOURS AT 200 P.S.I. UNACCEPTABLE LEAKAGE SHALL BE REPAIRED AND WATER LINE SHALL BE RETESTED PRIOR TO ACCEPTANCE BY FAYETTE COUNTY WATER SYSTEM. MAIN MUST BE DISINFECTED PRIOR TO BEING PLACED IN SERVICE.

11. TOP OF CURBS SHALL BE PERMANENTLY MARKED AND PAINTED BLUE AT MAIN AND SERVICE CROSSINGS, AS WELL AS, VALVE AND METER LOCATIONS.

12. WATERLINE CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL, INCLUDING SIGNAGE AND FLAGMEN, WHILE WORKING WITHIN THE RIGHT OF WAY OF ANY EXISTING ROAD.

13. WATERLINE CONTRACTOR PERFORMING ANY WORK WITHIN AN EXISTING RIGHT OF WAY MUST COMPLY WITH THE MUTCD 2003 EDITION WITH REVISIONS NUMBER 1 AND 2 INCORPORATED, DATED DECEMBER 2007. FLAGGERS MUST POSSESS A CURRENT CERTIFICATION CARD. DOCUMENTATION SHALL BE AVAILABLE UPON REQUEST BY ANY COUNTY EMPLOYEE.

14. WATER TO BE PROVIDED BY FAYETTE COUNTY WATER SYSTEM.

15. ALL TIE-INS SHALL BE COORDINATED WITH FAYETTE COUNTY WATER SYSTEM. EXISTING VALVES SHALL BE OPERATED BY COUNTY PERSONNEL ONLY.

16. CONTRACTOR MUST NOTIFY FAYETTE COUNTY WATER SYSTEM 24 HOURS PRIOR TO BEGINNING CONSTRUCTION OR REQUESTING INSPECTIONS. ALL WORK MUST BE INSPECTED PRIOR TO BACKFILL AND COMPACTION. ANY WORK COVERED PRIOR TO INSPECTION IS SUBJECT TO REJECTION UNTIL IT HAS BEEN EXPOSED AND INSPECTED BY FAYETTE COUNTY WATER PERSONNEL.

17.NO TRENCHES OR PITS ARE TO BE LEFT OPEN OVERNIGHT OR THROUGH A WEEKEND. IF CREW VACATES JOB SITE DURING DAYTIME HOURS, A PROPERLY CONSTRUCTED, HIGHLY VISIBLE BARRICADE MUST BE ERECTED.

18. WHILE THE EXCAVATION IS OPEN, UNDERGROUND INSTALLATIONS SHALL BE PROTECTED, SUPPORTED OR REMOVED AS NECESSARY TO SAFEGUARD EMPLOYEES.

19. MEANS OF EGRESS FROM TRENCH EXCAVATIONS. A STAIRWAY, LADDER, RAMP OR OTHER SAFE MEANS OF EGRESS SHALL BE LOCATED IN TRENCH EXCAVATIONS THAT ARE 4 FEET OR MORE IN DEPTH SO AS TO REQUIRE NO MORE THAN 25 FEET OF LATERAL TRAVEL FOR EMPLOYEES.

20.CONTACT MATT BERGEN AT THE FAYETTE COUNTY WATER SYSTEM TO SCHEDULE A PRECONSTRUCTION MEETING PRIOR TO BEGINNING ANY WORK. PHONE: 770-320-6020 FAX: 770-719-5576

21.ALL CONTRACTORS MUST HAVE A CERTIFIED COMPETENT PERSON ON SITE WHILE WORK IS BEING PERFORMED. DOCUMENTATION SHALL BE AVAILABLE UPON REQUEST BY ANY COUNTY EMPLOYEE.

22.ALL CONTRACTORS PERFORMING ANY LAND DISTURBING ACTIVITY SHALL HAVE ATTENDED THE GSWCC SUB CONTRACTOR AWARENESS COURSE WHEN WORKING IN A COMMON DEVELOPMENT WHERE THE PRIMARY PERMITTEE HAS OBTAINED A LEVEL 1A CERTIFICATION. THE PRIMARY PERMITTEE IS REQUIRED TO HAVE A LEVEL 1A CERTIFIED REPRESENTATIVE ON SITE AT ALL TIMES. DOCUMENTATION SHALL BE AVAILABLE UPON REQUEST BY ANY COUNTY EMPLOYEE.

23.ANY CONTRACTOR PERFORMING ANY LAND DISTURBING ACTIVITY UNDER CONTRACT FOR FAYETTE COUNTY WATER SYSTEM SHALL BE CONSIDERED THE SECONDARY PERMITTEE FOR EACH PROJECT. THE CONTRACTOR SHALL BE REQUIRED TO HAVE A GSWCC LEVEL 1A CERTIFIED REPRESENTATIVE ON SITE AT ALL TIMES. DOCUMENTATION SHALL BE AVAILABLE UPON REQUEST BY ANY COUNTY EMPLOYEE.

24.BEFORE RELEASE OF THE WATER LINES, 2 CERTIFIED AS - BUILTS (24 X 36) MUST BE SUBMITTED ALONG WITH 2 SIGNED FINAL PLATS OR FINAL SITE PLANS. ONE ELECTRONIC COPY OF EACH DOCUMENT SHOULD BE SENT TO THE INSPECTOR UPON ACCEPTANCE.

1. BENCHMARK FOR CONSTRUCTION HAS BEEN PROVIDED ON SHEET C-101

2. ALL LABOR, MATERIALS, AND METHODS OF CONSTRUCTION SHALL BE IN STRICT ACCORDANCE WITH THE MINIMUM ENGINEERING AND CONSTRUCTION STANDARDS ADOPTED BY THE FAYETTE COUNTY. WHERE CONFLICTS OR OMISSIONS EXIST. THE FAYETTE COUNTY STANDARDS SHALL DICTATE. SUBSTITUTIONS AND DEVIATION FROM PLANS AND SPECIFICATIONS SHALL BE PERMITTED ONLY WHEN WRITTEN APPROVAL HAS BEEN ISSUED BY THE ENGINEER.

INSTALLATION.

4. ALL MATERIALS AND CONSTRUCTION TO BE IN ACCORDANCE WITH THE FAYETTE COUNTY DEVELOPMENT REGULATIONS, LATEST 8. THE REINFORCED CONCRETE PIPE SHALL BE CLASS III WITH WALL THICKNESS "B" CONFORMING TO ASTM C - 76 OR AWWA 302 - 74 EDITION, UNLESS OTHERWISE WAIVED.

5. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL REQUIRED PERMITS ARE OBTAINED AND IN HAND BEFORE BEGINNING ANY CONSTRUCTION. NO CONSTRUCTION OR FABRICATION OF ANY ITEM SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED ALL PLANS AND ANY OTHER DOCUMENTATION FROM ALL OF THE PERMITTING AND ANY OTHER REGULATORY AUTHORITIES. ANY PENALTIES, STOP WORK ORDERS OR ADDITIONAL WORK RESULTING FROM THE CONTRACTOR BEING IN VIOLATION OF THE REQUIREMENTS ABOVE, SHALL BE FULLY BORNE BY THE CONTRACTOR.

GENERAL (CONTINUED)

6. THE LOCATION OF ALL EXISTING UTILITIES AND STORM DRAINAGE SHOWN ON THE PLANS HAVE BEEN DETERMINED FROM THE BEST INFORMATION AVAILABLE AND ARE GIVEN FOR THE CONVENIENCE OF THE CONTRACTOR. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR INACCURACY. PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITY IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE VARIOUS UTILITIES AND TO MAKE THE NECESSARY ARRANGEMENTS FOR ANY RELOCATION OF THESE UTILITIES WITH THE OWNER OF THE UTILITY. THE CONTRACTOR SHALL EXERCISE CAUTION WHEN CROSSING UNDERGROUND UTILITIES, WHETHER SHOWN ON THE PLAN OR LOCATED BY THE UTILITY COMPANY. ALL UTILITIES WHICH INTERFERE WITH THE PROPOSED CONSTRUCTION SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER FIRST. ANY FEES ASSOCIATED WITH UTILITY RELOCATIONS SHALL BE BORNE IN ACCORDANCE WITH RESPECTIVE UTILITY COMPANY STANDARDS. IT IS REQUESTED UTILITY COMPANIES MOVE THEIR PARTICULAR UTILITIES. ANY DELAY OR INCONVENIENCE CAUSED TO THE CONTRACTOR BY THE RELOCATION OF THE VARIOUS UTILITIES SHALL BE INCIDENTAL TO THE CONTRACT AND NO EXTRA COMPENSATION WILL BE ALLOWED.

THE CONTRACTOR SHALL SCHEDULE A PRECONSTRUCTION MEETING TO BE HELD BETWEEN FAYETTE COUNTY, UTILITIES, ENGINEER OF RECORD, AND CONTRACTOR PRIOR TO COMMENCEMENT OF CONSTRUCTION.

THE SEQUENCE OF CONSTRUCTION SHALL BE SUCH THAT ALL UNDERGROUND INSTALLATIONS OF EVERY KIND, INCLUDING LANDSCAPE SPRINKLERS, SHALL BE PLACED BENEATH THE PAVEMENT AND ITS EDGES PRIOR TO THE CONSTRUCTION OF THE PAVEMENT. THE PAVEMENT SHALL NOT BE CUT WITHOUT PRIOR APPROVAL OF THE ENGINEER.

THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 48 HOURS PRIOR TO BEGINNING CONSTRUCTION AND AT LEAST 48 HOURS HOURS BEFORE REQUIRED INSPECTION ON EACH AND EVERY PHASE OF WORK. THE CONTRACTOR SHALL NOTIFY THE ENGINEER A MINIMUM OF 48 HOURS NOTICE PRIOR TO ANY SCHEDULED TESTING. NO PRESSURE TESTING, OR FINAL TESTING WILL BE ACCEPTED UNLESS WITNESSED BY THE ENGINEER'S REPRESENTATIVE.

10. ALL CONTRACTORS, CITY REPRESENTATIVES, COUNTY REPRESENTATIVES, AND UTILITY COMPANIES ARE RESPONSIBLE FOR THEIR RESPECTIVE SURVEYING AND LAYOUT FROM BENCHMARK PROVIDED ON CONSTRUCTION PLANS. ANY SURVEY MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE REPLACED UPON COMPLETION OF THE WORK BY A REGISTERED

11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING ANY CONSTRUCTION ACTIVITIES FROM TAKING PLACE OUTSIDE OF THE LIMITS OF CONSTRUCTION SHOWN ON THE PLANS. ANY ON-SITE OR OFFSITE AREAS DISTURBED SHALL BE RESTORED TO

12. THE CONTRACTOR SHALL MAINTAIN A CURRENT SET OF CONSTRUCTION PLANS AND ALL PERMITS ON THE JOB SITE DURING ALL PHASES OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE TWO (2) SETS OF RECORD DRAWINGS TO THE ENGINEER OF RECORD WITHIN TWO (2) WEEKS AFTER CONSTRUCTION HAS BEEN COMPLETED ON EACH PHASE

13. TOPOGRAPHIC INFORMATION SHOWN ON THESE PLANS WERE TAKEN FROM SURVEY PROVIDED BY: ROCHESTER AND ASSOCIATES, INC. 10/02/17.

14. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE EXISTING SITE CONDITIONS OF SOIL PRIOR TO N.T.P. CONSTRUCTION TO DETERMINE IF ANY OFF SITE MATERIALS WILL NEED TO BE IMPORTED TO ACHIEVE THE GRADES SPECIFIED ON THE PLANS.

15. CLEAR AREAS INDICATED SHALL BE COMPLETELY CLEAR OF ALL TIMBER, BRUSH, STUMPS, ROOTS, GRASS, WEEDS, RUBBISH, AND ALL OTHER DEBRIS AND OBSTRUCTIONS RESTING ON OR PROTRUDING THROUGH THE SURFACE OF THE GROUND.

16. PRIOR TO BID PREPARATION, THE CONTRACTOR MUST BECOME FAMILIAR WITH THE OVERALL SITE CONDITIONS AND PERFORM ADDITIONAL INVESTIGATIONS AS DETERMINED NECESSARY TO UNDERSTAND THE LIMIT AND DEPTH OF EXPECTED ORGANIC SILT PEAT AREAS, ADEQUACY OF EXISTING MATERIALS AS FILL, DEWATERING REQUIREMENTS, CLEAN FILL REQUIRED FROM OFFSITE, AND MATERIALS TO BE DISPOSED OF OFFSITE, ALL OF WHICH WILL AFFECT HIS PRICING. ANY DELAY, INCONVENIENCE, OR EXPENSE CAUSED TO THE CONTRACTOR DUE TO INADEQUATE INVESTIGATION OF EXISTING CONDITIONS SHALL BE INCIDENTAL TO THE CONTRACT, AND NO EXTRA COMPENSATION WILL BE ALLOWED. THE MATERIALS ANTICIPATED TO BE ENCOUNTERED DURING CONSTRUCTION MAY REQUIRE DRYING PRIOR TO USE AS BACKFILL, AND THE CONTRACTOR MAY HAVE TO IMPORT MATERIALS. AT NO EXTRA COST. FROM OFFSITE TO MEET THE REQUIREMENTS FOR COMPACTION AND PROPER FILL.

DEMOLITION:

1. THE CONTRACTOR SHALL OBTAIN NECESSARY PERMITS AND LICENSES FOR PERFORMING THE DEMOLITION WORK AND SHALL FURNISH A COPY OF THESE ITEMS TO THE ENGINEER PRIOR TO COMMENCING THE WORK. THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE PERMITS.

THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES OR LOCAL AUTHORITIES FURNISHING GAS. WATER. ELECTRICAL. TELEPHONE, OR SEWER SERVICE SO THEY CAN REMOVE, RELOCATE, DISCONNECT, CAP OR PLUG THEIR EQUIPMENT IN ORDER TO FACILITATE DEMOLITION.

3. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL TREES, STRUCTURES, AND UTILITIES NOT MARKED FOR REMOVAL OR DEMOLITION AND SHALL PROMPTLY REPAIR ANY DAMAGE AS DIRECTED BY THE ENGINEER AT NO COST TO THE OWNER.

THE CONTRACTOR SHALL REMOVE PAVING MARKED FOR DEMOLITION WHICH INCLUDES ALL ASPHALT, CONCRETE, BASE, AND RETAINING WALLS (INCLUDING THE FOOTERS).

THE CONTRACTOR SHALL REMOVE TREES MARKED FOR REMOVAL WHICH INCLUDES THE ROOTS ASSOCIATED WITH THE TREE.

TREES NOT MARKED FOR REMOVAL SHALL BE PROTECTED IN ACCORDANCE WITH THE FAYETTE COUNTY REGULATIONS. 6. THE CONTRACTOR SHALL REMOVE UNSALVAGEABLE MATERIALS AND YARD WASTE FROM THE SITE IMMEDIATELY AND DISPOSE

OF IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE, AND LOCAL REGULATIONS.

7. THE CONTRACTOR SHALL SAW-CUT A SMOOTH STRAIGHT EDGE ON ANY PAVEMENT PROPOSED FOR DEMOLITION PRIOR TO ITS REMOVAL. PRIOR TO CONNECTING PROPOSED PAVEMENT TO EXISTING PAVEMENT, THE CONTRACTOR SHALL ENSURE THAT THE EDGE OF THE EXISTING PAVEMENT IS STRAIGHT AND UNIFORM.

EARTHWORK, GRADING, STABILIZATION, PAVING AND DRAINAGE:

1. COMPACT ALL UTILITY TRENCHES WITHIN ROADWAYS TO 98% OF THE MODIFIED PROCTOR MAXIMUM DENSITY (AASHTO T - 180) AND TO 95% WITHIN OTHER AREAS.

2. ALL ORGANIC SOILS BELOW UTILITY TRENCHES SHALL BE REMOVED AND REPLACED WITH SUITABLE MATERIAL AND COMPACTED TO NO LESS THAN 98% OF THE MODIFIED PROCTOR MAXIMUM DENSITY (AASHTO T - 180).

STABILIZED SUBGRADE TO MEET SPECIFIED REQUIREMENTS.

4. ASPHALTIC CONCRETE TO GDOT STANDARD SPECIFICATION (LATEST EDITION) SECTION 400 AND FAYETTE COUNTY, WHICHEVER IS GREATER.

5. ALL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC.

FOR MITERED END SECTIONS.

ALL CONCRETE FLUMES, WALKS, AND CURBS SHALL BE CONSTRUCTED WITH 3000 PSI CONCRETE.

3. SHOP DRAWINGS OF ALL MATERIALS BEING USED SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO 7. ALL ON-SITE AREAS DISTURBED BY THE CONSTRUCTION SHALL BE STABILIZED WITH SOD (SAME AS SURROUNDING AREA OR BETTER) OR APPROVED EQUAL. CONTRACTOR IS RESPONSIBLE FOR IRRIGATION OF PERMANENT GRASSING.

> AND GASKETS SHALL BE IN ACCORDANCE WITH ASTM C - 443 OR ASTM D - 412. 9. ALL PIPE CALL OUTS ARE MEASURED CENTER LINE TO CENTER LINE FOR MANHOLES AND INLETS AND FROM THE END OF THE PIPE

> 10. ALL DEWATERING COSTS ASSOCIATED WITH THE INSTALLATION AND CONSTRUCTION OF THE UNDERGROUND UTILITIES; STORM WATER PIPES AND MANHOLES; SANITARY SEWER MAINS, FORCE MAINS, MANHOLES, AND LIFT STATIONS; AND STORM WATER MANAGEMENT SYSTEMS SHALL BE INCLUDED AS PART OF THE CONSTRUCTION BID COSTS. THE CONTRACTOR SHALL SUBMIT FOR WATER USE PERMITS IF REQUIRED FOR DEWATERING ACTIVITIES.

EARTHWORK, GRADING, STABILIZATION, PAVING AND DRAINAGE (CONTINUED)

11. ALL PIPES SHALL HAVE 3 FEET MINIMUM COVER UNLESS OTHERWISE SPECIFIED IN PLANS, CONTRACTOR SHALL TAKE CARE TO PROVIDE PROPER GRADE ELEVATIONS AND ALIGNMENTS.

12. THE CONTRACTOR MUST INSTALL AND MAINTAIN GRASS OR SOD ON EXPOSED SLOPES WITHIN 48 HOURS OF COMPLETED FINAL GRADES, AS NOTED ON PLANS, AND AT ANY OTHER TIME AS NECESSARY TO PREVENT EROSION, SEDIMENTATION OR TURBID DISCHARGES TO ANY DOWNSTREAM WATER BODY, WETLAND, OR OFF-SITE PROPERTY. SODDING ON SLOPES 3:1 AND STEEPER SHALL BE STAKED.

13. THE CONTRACTOR SHALL TAKE ALL MEASURES NECESSARY TO CONTROL TURBIDITY AND SEDIMENT INCLUDING, BUT NOT LIMITED TO, THE INSTALLATION OF TURBIDITY BARRIERS AND SILT FENCES AT ALL LOCATIONS WHERE THE POSSIBILITY OF TRANSFERRING SUSPENDED SOLIDS INTO THE RECEIVING WATER BODY EXISTS DUE TO THE PROPOSED WORK. TURBIDITY AND SEDIMENT BARRIERS MUST BE MAINTAINED AT ALL LOCATIONS UNTIL CONSTRUCTION IS COMPLETED AND DISTURBED SOIL AREAS ARE STABILIZED. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR REMOVING THE BARRIERS.

OTHER UTILITY INFORMATION:

THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES WHICH MAY HAVE THEIR UTILITIES WITHIN THE CONSTRUCTION AREAS TO LOCATE THEIR FACILITIES IN THE FIELD FORTY-EIGHT (48) HOURS PRIOR TO BEGINNING CONSTRUCTION.

DUCTILE IRON PIPE SHALL BE ENCASED IN POLYETHYLENE TWENTY-FIVE (25) FEET ON EACH SIDE OF ANY PERPENDICULAR CROSSING OF METALLIC GAS MAINS OR ANY OTHER CATHODICALLY PROTECTED PIPELINE AND FOR LOCATIONS PARALLEL TO AND WITHIN TEN FEET OF METALLIC GAS MAINS OR OTHER CATHODICALLY PROTECTED PIPE AND THROUGH THE AREA OF INFLUENCE OF CATHODIC PROTECTION ANODE BED.

SPILL CONTROL NOTES:

IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS NOTES OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

a. MANUFACTURERS' RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.

b. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.

c. SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF SIZE.

d. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED.

e. THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY SITE OPERATIONS WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR.

PETROLEUM BASED PRODUCTS - CONTAINERS FOR PRODUCTS SUCH AS FUELS, LUBRICANTS, AND TARS WILL BE INSPECTED DAILY FOR LEAKS AND SPILLS. THIS INCLUDES ON-SITE VEHICLE AND MACHINERY DAILY INSPECTIONS AND REGULAR PREVENTATIVE MAINTENANCE OF SUCH EQUIPMENT. EQUIPMENT MAINTENANCE AREAS WILL BE LOCATED AWAY FROM STATE WATERS, NATURAL DRAINS AND STORM WATER DRAINAGE INLETS. IN ADDITION, TEMPORARY FUELING TANKS SHALL HAVE A SECONDARY CONTAINMENT LINER TO PREVENT/MINIMIZE SITE CONTAMINATION. DISCHARGE OF OILS, FUELS AND LUBRICANTS IS PROHIBITED. PROPER DISPOSAL METHODS WILL INCLUDE IN A SUITABLE CONTAINER AND DISPOSAL AS REQUIRED BY LOCAL AND STATE REGULATIONS.


Ш








CERT. # 0000073529

Project No.: 200-01297-1800 Desianed Bv Drawn By: hecked By:











<u>890</u> DOGWOOD TRAIL € STA |2+36 —— ∕− GUARDRAIL GUARDRAIL EXISTING UNDERGROUND COMMUNICATION LINES TO BE RELOCATED PROPOSED 8" DIP WATER LINE — – 100-YEAR WATER SURFACE ELEVATION (CULVERT FLOWING FULL) EXISTING 8" WATER LINE TO BE RELOCATED — ✓ FINISHED GRADE 875 870 / EXISTING GAS LINE TO BE RELOCATED — − 25-YEAR WATER SURFACE ELEVATION EXISTING GRADE HEADWALL ⁄— HEADWAL<mark>l</mark> INV = 858 00' ----1.5' THICK TYPE 3 RIPRAP APRON -----(SCOUR COUNTERMEASURES DESIGN TO BE INCLUDED WITH CULVERT DESIGN SUBMITTAL) — ─ 1.5' THICK TYPE 3 RIPRAP APRON (SCOUR COUNTERMEASURES 80 LF 48'X14' CONCRETE BOTTOMLESS ARCH CULVERT @ 2.5% DESIGN TO BE INCLUDED WITH (FOUNDATION DESIGN BASED ON GEOTECHNICAL REPORT TO CULVERT DESIGN SUBMITTAL) BE INCLUDED WITH CULVERT DESIGN SUBMITTAL) 1+00 2+80.91 0+00 2+00 STORM LINE SYSTEM PROFILE SCALE: HORIZ: 1"= 20' VERT: 1"= 5' 890 890 <u>885</u> FLOW SUMMARY TABLE OUTLET VELOCITY DOWNSTREAM STORM FLOW (CFS) / INV = 87 1.25 → <u>875</u> <u>875</u> VELOCITY (FPS) FREQUENCY 33 LF 12" CMP @ 5.3% 25-YEAR 4994 8.7 8.0 50-YEAR 10.7 6104 8.4 97 LF 18" CMP 100-YEAR 12.8 7290 <u>870</u> 870 DRAINAGE AREA = 237 ACRES STREAM SLOPE = 0.93% 27 LF 18" CMP @ 4.2% <u>865</u> 18" CMP PENETRATION INTO WINGWALL INV. = 865.79
STA. 11+62.6 - EXISTING CMP DRIVEWAY CULVERT INV. = 873.01 EXST PROP Designed By: Drawn By: 10+00 11+00 11+72.59 Checked By: STORM LINE SYSTEM PROFILE SCALE: HORIZ: 1"= 20' VERT: 1"= 5'







GRADING AND DRAINAGE PROFILE

Project No.: 200-01297-18009









VALVE MARKER DETAIL DETAIL SCALE: N.T.S.

SCALE: N.T.S.

DEADMAN







DETAIL

SCALE: N.T.S.


PSI SD	RESSURE IIL PRESS 2000 PSF	SURE =
PIPE SIZE X	Α	В
6′′	2'-0''	2'-0''
8′′	2′-6′′	2'-6''
10′′	3′-6′′	3'-6''
12′′	4'-0''	4'-0''
14′′	4'-6''	4'-6''
16′′	5′-0′′	5′-0′′
18′′	6'-0''	6'-0''
20′′	6'-6''	6'-6''
24′′	7′-6′′	7′-6′′








ROADWAY TO MATCH FAYETTE COUNTY TYPICAL CROSS SECTION FROM STA. 1+57 TO 3+15



DETAIL SCALE: N.T.S.

NOT USED







- FINISHED GRADE RESTRAINED JOINTS_ SEE RESTRAINED JOINT SCHEDULE MINIMUM DISTANCE (SEE TABLE \leq SEE PIPE BELOW) BELOW) BEDDING SEE UTILITY SEPARATION **DETAILS** UTILITY TYPE REQUIREMENTS ON DETAILS (SEE TABLE -1 AND 2 , SHEET C-504 BELOW) UTILITY -OTHER THAN SEWER MAINS UTILITY TYPE MINIMUM DISTANCE NOTE: 18" MIN SEPARATION SANITARY SEWER OR 10'-0" MIN.

> RESTRAINED JOINT UTILITY CROSSING FOR UTILITIES OTHER THAN SEWER MAINS

FORCE MAIN

OTHER THAN SEWER


	STRAII	NED LI	ENGTH E	ACH SIDE	OF RES	TRAIN	ED FITTIN	NG (FEET)	1			REST	RAINED	LENGT	H FOR I	REDUC	ERS			
PIPE DIA			DIP				PVC													
Inches)	90°	45°	22-1/2°	11-1/4°	90°	45°	22-1/2°	11-1/4°	3	4	6	8	10	12	16	20	24	30	36	
4	35	15	10	5	55	25	15	10	40	-	-	-		-	-	-	-	-	-	PV
6	55	25	10	5	80	35	20	10	50	45	-	-		-	-	-	-	-	-	PV
8	65	30	15	10	90	40	20	10	75	70	40	-	-	-	-	-	-	-	-	PV
10	80	35	20	10	110	50	25	15	95	90	70	40	-	-	-	-	-	-	-	PV
12	95	40	20	10	130	55	30	15	120	115	100	75	40	-	-	-	-	-	-	PV
16	120	50	25	15	165	70	35	20	160	155	140	125	100	70	-	-	-	-	-	PV
20	150	65	30	15	200	85	40	20	200	195	185	170	150	130	75	-	-	-	-	PV
24	160	70	35	20	210	90	45	25	160	155	150	140	135	120	90	50	-	-	-	DIF
30	190	80	40	20	250	105	50	25	195	190	185	180	170	160	120	105	70	-	-	DIF
36	220	95	45	25	-	-	-	-	225	220	215	210	205	195	180	150	125	70	-	DIF
42	245	105	50	25	-	-	-	-	245	240	235	230	225	220	205	180	155	105	50	DIF
48	260	120	60	30	-	-	_	-	255	250	245	240	235	230	215	195	175	125	70	DII

RESTRAINED LENGTHS FOR DEAD ENDS, BRANCHES AND HDPE TO PVC TRANSITIONS LENGTH OF RESTRAINED JOINT FOR LARGER DIAMETER PIPE SHALL BE THE SAME AS FOR 90° BENDS. IN-LINE VALVES SHALL BE RESTRAINED 20' EACH SIDE OF THE VALVE. (IF A JOINT FALLS AT THE MAXIMUM DISTANCE, IT SHALL BE RESTRAINED). TABLE BASED ON IRON FITTINGS. TEST PRESSURE 150 PSI.

RESTRAINED JOINT SCHEDULE

5 DETAIL SCALE: N.T.S.


TREE PROTECTION "SNOW" FENCE



- 1. USE TRENCHER (I.E. DITCH WITCH) TO CUT A 4"-5" W X 18" D TRENCH ALONG DRIP LINE (LIMIT OF CLEARING) AND BACKFILL WITH SAND AND LIGHTLY COMPACT.
- 2. SPACE STAKES AT INTERVALS SUFFICIENT TO MAINTAIN ALL FENCING OUT OF DRIP LINE OR AS SHOWN BY ENGINEER (SET STAKES NO GREATER THAN 6 FEET
- ON CENTER-REBAR IS NOT TO BE USED FOR STAKES). 3. MAINTAIN FENCE BY REPAIRING AND/OR REPLACING DAMAGED FENCE. DO NOT
- REMOVE FENCING PRIOR TO LANDSCAPING OPERATIONS.

 4. DO NOT STORE OR STACK MATERIALS, EQUIPMENT, OR VEHICLES WITHIN FENCED
- 5. FENCE SHALL BE ORANGE VINYL "SNOW FENCE" 4' HIGH MINIMUM.

DETAIL SCALE: N.T.S.




FOR STORM DRAIN CROSSINGS

NOIT

Project No.: 200-01297-18009 Designed By: Drawn By: Checked By:

^{**} DIMENSION "G" TO BE 6' FOR DOGWOOD TRAIL



SECTION B-B

DETAIL

SCALE: N.T.S.

DETAIL "B"

NO SCALE

G.L.O. (SUBMITTED)

STATE DESIGN POLICY ENGINEER

B.R.E. (APPROVED) Margaret B Parkle

NUMBER

4384

(FLARED, NON-ENERGY-ABSORBING)

DETAIL

SCALE: N.T.S.

NOTE: TP. I ANCHOR
DETAILS ARE SIMILAR FOR BOTH SIDES, BUT LENGTHS (SEE DETAIL A)
AND ANCHORAGE/TERMINAL TYPES MAY DIFFER.

GUARDRAIL LOCATION AT END OF NARROW BRIDGE

(NOTE: DETAILS NOT SHOWN HERE ARE SIMILAR TO THOSE AT TOP LEFT.)

31 INCH GUARDRAIL HEIGHT

4388

DES. G.L.O.
DRW. G.L.O.
CIKK, B.R.E.
REVIEWB.A.S.
CIKE PRINCER

CAPPROVED! WAYGRAF B PURELO
CIKE PRINCER


교교 SCALE AS SHOWN

Bar Measures 1 inch

Designed By:


Checked By:

Drawn By:




TECH





CONSTRUCTION DETAILS



(PERMANENT VEGETATION)

Ds3

DISTURBED AREA

STABILIZATION (TMP. SEEDING)

2014 MANUAL FOR EROSION AND SEDIMENT CONTROL (GREEN BOOK)

Figure 6-27.2


Ds2


EROSION CONTROL NOTES


- EROSION CONTROL PRACTICES MUST COMPLY WITH THE MINIMUM BEST MANAGEMENT PRACTICES FOR EROSION CONTROL AND SHALL COMPLY WITH THE STANDARDS AND SPECIFICATIONS IN THE "MANUAL FOR EROSION CONTROL AND SEDIMENT CONTROL IN GEORGIA"
- 2. EROSION AND SEDIMENT CONTROL DEVICES MUST BE INSTALLED AND INSPECTED PRIOR TO ANY GRADING ON SITE
- DISTURBED AREAS LEFT IDLE FOR FIVE DAYS, AND NOT TO FINAL GRADE, WILL BE ESTABLISHED WITH TEMPORARY MULCH (DS1) OR VEGETATION (DS2). DISTURBED AREAS LEFT IDLE FOR TWO WEEKS OR MORE WILL BE ESTABLISHED WITH PERMANENT VEGETATION (DS3). ALL AREAS AT FINAL GRADE WILL BE ESTABLISHED WITH PERMANENT VEGETATION IMMEDIATELY UPON COMPLETION. WHEN HAND PLANTING, MULCH (HAY OR STRAW) SHOULD BE UNIFORMLY SPREAD OVER SEEDED AREA WITHIN 24 HOURS OF SEEDING. DURING UNSUITABLE GROWING SEASONS, MULCH WILL BE USED AS A TEMPORARY COVER (DS3). ON SLOPES THAT ARE 2:1 OR STEEPER, MULCH WILL BE ANCHORED.
- 4. IN CONCENTRATED FLOW AREAS: ALL SLOPES STEEPER THAN 2.5:1, HEIGHT TEN FEET OR GREATER, AND CUTS AND FILLS WITHIN STREAM BUFFER, STABILIZE WITH THE APPROPRIATE EROSION CONTROL MATTING OR BLANKET
- 5. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND-DISTURBING ACTIVITIES. EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- SEDIMENT/EROSION CONTROL DEVICES MUST BE CHECKED AFTER EACH STORM EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE THIRD THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF NEW CHANNELS HAVE DEVELOPED.
- THE USE OF POLYMERS (PAMS) IS ACCEPTED AS A BMP AS RECOMMENDED BY THE STATE SOIL & WATER CONSERVATION COMMISSION BMP "GREEN BOOK". POLYMERS USED TO STABILIZE CONSTRUCTION SITES MUST BE USED IN CONJUNCTION WITH MULCHING AND OR HYDROSEEDING.
- 8. MULCH, TEMPORARY VEGETATION, AND PERMANENT (PERENNIAL) VEGETATION SHALL BE COMPLETED ON ALL EXPOSED AREAS WITHIN 14 DAYS AFTER DISTURBANCE.
- ADDITIONAL EROSION CONTROL DEVICES MAY BE REQUIRED BY ENGINEER DURING CONSTRUCTION.
- 10. DUE TO THE NATURE AND LOCATION OF THE CONSTRUCTION ACTIVITY, PROVIDING SEDIMENT STORAGE FOR 67 CUBIC YARDS OF SEDIMENT PER ACRE DISTURBED IS NOT FEASIBLE. APPROPRIATE BMPS THAT LIMIT THE TRANSPORT OF SEDIMENT FROM THE SITE WILL BE UTILIZED. THERE BMPS INCLUDE BUT ARE NOT LIMITED TO SILT FENCE AND TEMPORARY MULCHING, GRASSING OR PERMANENT GRASSING FOR THE DISTURBED AREAS OF THE PROJECT.
- 11. THE RATIONAL METHOD RUNOFF COEFFICIENT FOR THE SITE PRIOR TO AND AFTER CONSTRUCTION IS C = 0.15


EROSION CONTROL CHECKLIST CERTIFICATIONS:

ALL STREAM BUFFER DISTURBANCES ARE ASSOCIATED WITH THE CULVERT REPLACEMENT. THE PROJECT DISTURBS LESS THAN 100 LINEAR FEET OF STREAM AND IS CLASSIFIED AS A UTILITY CROSSING. AS SUCH NO USACE PERMIT OR BUFFER VARIANCE IS ANTICIPATED.


















Project No.: 200-01297-1800 Designed By Drawn By: Checked By:

CONTAILS

SION

RO

THE CONTRACTOR SHALL OBSERVE THE PROJECT SEQUENCE SHOWN ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN CAREFUL SCHEDULING AND PERFORMANCE TO INSURE THAT LAND STRIPPED OF ITS NATURAL COVER IS EXPOSED ONLY IN SMALL QUANTITIES.

THE OWNER AGREES TO PROVIDE AND MAINTAIN OFF-STREET PARKING ON THE SUBJECT PROPERTY DURING THE ENTIRE CONSTRUCTION PERIOD.

NO STAGING AREAS, MATERIAL STORAGE, CONCRETE WASH OUT AREAS, OR DEBRIS BURN AND BURIAL HOLES SHALL BE LOCATED WITHIN 500 FEET OF DESIGNATED TREE PROTECTION AREAS.

A COPY OF THE APPROVED LAND DISTURBANCE PLAN AND PERMIT SHALL BE PRESENT ON THE SITE AT ALL TIMES.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.

PRIOR TO COMMENCING LAND DISTURBING ACTIVITY, THE LIMITS OF LAND DISTURBANCE AND ALL STREAM BUFFERS SHALL BE CLEARLY AND ACCURATELY DEMARCATED WITH STAKES, RIBBONS, OR OTHER APPROPRIATE MEANS. THE LOCATION AND EXTENT OF ALL AUTHORIZED LAND DISTURBANCE ACTIVITY SHALL BE DEMARCATED FOR THE DURATION OF THE CONSTRUCTION ACTIVITY. NO LAND DISTURBANCE SHALL OCCUR OUTSIDE THE APPROVED LIMITS INDICATED ON THE APPROVED PLANS.

PRIOR TO ANY OTHER CONSTRUCTION, A STABILIZED CONSTRUCTION ENTRANCE/EXIT SHALL BE CONSTRUCTED AT EACH POINT OF ENTRY TO OR EXIT FROM THE SITE OR ONTO ANY PUBLIC ROADWAY.

THE FOLLOWING INITIAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED PRIOR TO ANY OTHER CONSTRUCTION ACTIVITY

THE CONSTRUCTION EXIT, CONSISTING OF A MINIMUM PAD SIZE OF 20 FEET BY 50 FEET WITH A MINIMUM OF 6" THICK STONE, SHALL BE PLACED AS SHOWN ON THE PLAN. THE STONE SIZE SHOULD CONSIST OF COURSE AGGREGATE BETWEEN 1-1/2" & 3-1/2" IN DIAMETER AND OVERLAID ON A GEOTEXTILE UNDERLINER. THE GEOTEXTILE UNDERLINER SHALL MEET THE REQUIREMENTS OF AASHTO M288-96, SECTION 7.3 SEPARATION REQUIREMENTS.

TYPE "C" SILT FENCE SHOULD BE INSTALLED AT THE PERIMETER OF THE DISTURBED AREA AS SHOWN ON THE PLAN. THE SILT FENCE SHOULD BE PLACED IN ACCORDANCE WITH THE MANUAL FOR EROSION CONTROL IN GEORGIA., TABLE 6-20.2. THE SILT FENCE SHOULD BE KEPT ERECT AT ALL TIMES AND REPAIRED WHEN REQUESTED BY THE SITE INSPECTOR OR THE PROJECT DESIGN PROFESSIONAL OF RECORD. SILT SHOULD BE REMOVED WHEN ACCUMULATION REACHES 1/2 HEIGHT OF THE BARRIER. THE PERIMETER SILT FENCE SHOULD BE INSPECTED DAILY FOR ANY FAILURES. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.

INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED ON ALL EXISTING STORM STRUCTURES AS SHOWN ON THE PLAN. SEE SEPARATE DETAILS FOR SPECIFICS ON TYPE OF INLET PROTECTION SPECIFIED.

TREE PROTECTION FENCING SHOULD BE INSTALLED PRIOR TO THE START OF ANY LAND DISTURBANCE ACTIVITY AND MAINTAINED UNTIL FINAL LANDSCAPE IS INSTALLED. THE TREE PROTECTION FENCING SHOULD BE INSPECTED DAILY. ANY FAILURES OF SAID FENCING SHOULD BE REPAIRED IMMEDIATELY.

AFTER INSTALLATION OF INITIAL EROSION CONTROL MEASURES, THE SITE CONTRACTOR SHALL SCHEDULE AN INSPECTION BY THE PROJECT DESIGN PROFESSIONAL. NO OTHER CONSTRUCTION ACTIVITIES SHALL OCCUR UNTIL THE PROJECT DESIGN PROFESSIONAL APPROVED THE INSTALLATION OF SAID EROSION CONTROL MEASURES. IF UNFORESEEN CONDITIONS EXIST IN THE FIELD THAT WARRANT ADDITIONAL EROSION CONTROL MEASURES, THE CONTRACTOR MUST CONSTRUCT ANY ADDITIONAL EROSION CONTROL DEVICES DEEMED NECESSARY BY THE SITE INSPECTION.

AFTER APPROVAL OF THE INITIAL EROSION CONTROL INSTALLATION, THE CONTRACTOR MAY PROCEED WITH CLEARING AND GRUBBING ACTIVITIES. AS CLEARING PERMITS THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SEDIMENT PONDS AND DIVERSION DIKES AS SHOWN ON THE CLEARING PHASE PLAN TO CONTROL EROSION AND STORM WATER RUN OFF.

THE DESIGN PROFESSIONAL WHO PREPARED THE EROSION CONTROL PLANS WILL INSPECT THE INSTALLATION OF BMPs WITHIN SEVEN DAYS AFTER INITIAL CONSTRUCTION ACTIVITY BEGINS.

THE CONTRACTOR CAN UTILIZE CLEARED TREES AS BARRIER BRUSH SEDIMENT CONTROL IN AREAS SHOWN ON THE PLAN WHERE INITIAL GRADING ACTIVITIES WILL

NO BURN OR BURY PITS SHALL BE PERMITTED ON THE CONSTRUCTION SITE WITHOUT WRITTEN PERMISSION BY THE OWNER AND/OR THE ENGINEER OF

ADDITIONAL SILT BARRIERS MUST BE PLACED AS SHOWN ON THE PLAN AS ACCESS IS OBTAINED DURING CLEARING. NO GRADING SHALL TAKE PLACE UNTIL SILT BARRIER INSTALLATION AND SEDIMENT PONDS ARE CONSTRUCTED AS SHOWN ON THE CLEARING PHASE EROSION CONTROL PLAN.

ALL SILT FENCE MUST MEET THE REQUIREMENTS OF SECTION 171-TEMPORARY SILT FENCE FOR THE DEPARTMENT OF TRANSPORTATION, STATE OF GEORGIA, STANDARD SPECIFICATIONS, LATEST EDITION.

ALL ITEMS IN THIS SECTION OF THE SPECIFICATIONS SHALL MEET THE REQUIREMENTS SET FORTH IN SECTION 161, 162, 163, AND 164 OF THE GEORGIA DOT STANDARD SPECIFICATIONS, FOR ROADS AND BRIDGES.

MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 14 DAYS OF LAND DISTURBANCE. THIS IS PRECLUDED BY SNOW COVER OR OTHER ADVERSE WEATHER CONDITIONS; STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE. WHERE CONSTRUCTION ACTIVITY WILL RESUME ON A PORTION OF THE SITE WITHIN 21 DAYS FROM WHEN ACTIVITIES CEASED (E.G., THE TOTAL TIME PERIOD THAT CONSTRUCTION ACTIVITY IS TEMPORARILY CEASED IS LESS THAN 21 DAYS) THEN STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE BY THE 14TH DAY AFTER CONSTRUCTION ACTIVITY TEMPORARILY CEASED.

ALL DISTURBED AREAS LEFT MULCHED AFTER 30 DAYS SHALL BE STABILIZED WITH TEMPORARY VEGETATION.

EROSION CONTROL PHASING NOTES

GRADING PHASE

THE FOLLOWING EROSION CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE PRELIMINARY GRADING PHASE OF CONSTRUCTION:

DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN CAREFUL SCHEDULING AND PERFORMANCE TO ENSURE THAT LAND STRIPPED OF ITS NATURAL COVER IS EXPOSED ONLY IN SMALL QUANTITIES AND THEREFORE LIMITED DURATIONS, BEFORE PERMANENT EROSION PROTECTION IS ESTABLISHED.

EARTHWORK OPERATIONS IN THE VICINITY OF STREAM BUFFERS SHALL BE CAREFULLY CONTROLLED TO AVOID DUMPING OR SLOUGHING INTO THE BUFFER AREAS.

EROSION CONTROL DEVICES SHALL BE INSTALLED IMMEDIATELY AFTER THE GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM THAT SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE DESIGN PROFESSIONAL IMMEDIATELY.

AFTER PRELIMINARY GRADING ACTIVITIES, THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SEDIMENT BASINS AND DIVERSION DIKES AS SHOWN ON THE PLAN. THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT PONDS UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT OF THE PONDS WHEN IT REACHES 1/2 DEPTH OF THE BASIN. SEE SEPARATE DETAILS FOR ADDITIONAL INFORMATION.

THE CONTRACTOR SHALL FURNISH AND MAINTAIN ALL NECESSARY BARRICADES WHILE ROADWAY FRONTAGE IMPROVEMENTS ARE BEING MADE.

TYPE "A" SILT FENCE SHOULD BE INSTALLED AT THE TOE OF ALL FILL SLOPES 10 FEET OR GREATER IN HEIGHT. THE SILT FENCE SHOULD BE PLACED IN ACCORDANCE WITH THE MANUAL FOR EROSION CONTROL IN GEORGIA., TABLE 6-20.2. THE SILT FENCE SHALL BE MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED ON THE SLOPE. SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES ½ HEIGHT OF THE BARRIER. ADDITIONALLY, DIVERSION DIKES SHALL BE CONSTRUCTED ALONG THE TOP OF ALL SAID FILL SLOPES WITH THE USE OF TEMPORARY DOWN DRAINS TO CONTROL STORM WATER RUN OFF AS SHOWN ON THE PLANS. SEE SEPARATE DETAILS TO ADDITIONAL INFORMATION.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING BARRIERS AT THE TOE OF SLOPES UNDER CONSTRUCTION. THESE BARRIERS SHALL BE AS SHOWN IN THE PLANS. THESE BARRIERS MAY BE RELOCATED AND REUSED AFTER PERMANENT SLOPE STABILIZATION BECOMES FULLY ESTABLISHED. AS THEY ARE RELOCATED, ANY DEFECTIVE MATERIALS IN THE BARRIER SHALL BE REPLACED. IN ADDITION, ALL DEBRIS AND SILT AT THE PREVIOUS LOCATED SHALL BE REMOVED.

CUT AND FILL SLOPES SHALL NOT EXCEED "2H:1V"

TYPE "C" SILT FENCE SHALL BE PLACED AT THE TOE OF ALL DIRT STOCK PILE

INLET SEDIMENT PROTECTION MEASURES SHALL BE INSTALLED AT ALL STORM STRUCTURES AS THEY ARE CONSTRUCTED. SEE PLANS AND DETAILS FOR INFORMATION ON THE TYPE OF INLET PROTECTION FOR EACH TYPE OF INLET STRUCTURE.

STORM DRAIN OUTLET PROTECTION SHALL BE PLACED AT ALL OUTLET HEADWALLS AS SOON AS THE HEADWALL IS CONSTRUCTED.

FINAL PHASE

THE FOLLOWING EROSION CONTROL MEASURES SHALL BE IMPLEMENTED DURING THE FINAL EROSION CONTROL PHASE OF CONSTRUCTION:

SEDIMENT SHALL NOT BE WASHED INTO INLETS. IT SHALL BE REMOVED FROM THE SEDIMENT TRAPS AND DISPOSED OF AND STABILIZED SO THAT IT WILL NOT ENTER THE INLETS AGAIN.

THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT PONDS UNTIL PERMANENT GROUND COVER IS ESTABLISHED. SEDIMENT SHALL BE CLEANED OUT OF THE PONDS WHEN IT REACHES 1/2 DEPTH OF THE BASIN.

AFTER CURBING, GRADED AGGREGATE BASE, AND PAVEMENT HAS BEEN INSTALLED, ALL INLET STRUCTURE SEDIMENT TRAPS ON SINGLE AND DOUBLE WING CATCH BASINS ALONG WITH ANY CURB INLETS SHALL BE REMOVED AND REPLACED WITH CURB FILTER INLET PROTECTION.

ALL ROADWAY AND PARKING SHOULDERS SHOULD BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED BEHIND CURBS.

EROSION CONTROL AND TREE PROTECTION MEASURES SHALL BE INSTALLED PRIOR TO ANY OTHER CONSTRUCTION ACTIVITY AND MAINTAINED UNTIL PERMANENT GROUND COVER IS ESTABLISHED.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH LAND-DISTURBING ACTIVITIES.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDED OR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

ANY DISTURBED ARE LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OF TEMPORARY SEEDING.

NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST **ACQUIRING THE NECESSARY VARIANCES AND PERMITS**

> 24 HOUR CONTACT: PHILIP MALLON 770-313-9855

GENERAL NOTES

STONE CHECK DAMS SHALL BE INSTALLED IN AREAS OF CONCENTRATED FLOWS AS IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE DESIGN SHOWN ON THE PLAN.

ALL DRAINAGE SWALES SHALL BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED.

ALL GRADED AREAS SHALL BE APPLIED WITH VEGETATIVE COVER AS SOON AS FINAL GRADE IS ACHIEVED.

MULCH OR TEMPORARY GRASSING SHALL BE APPLIED TO ALL EXPOSED AREAS WITHIN 14 DAYS OF LAND DISTURBANCE.

SEDIMENT AND EROSION CONTROL MEASURES SHOULD BE CHECKED AFTER EACH RAIN EVENT. EACH DEVICE IS TO BE MAINTAINED OR REPLACED IF SEDIMENT ACCUMULATION HAS REACHED ONE HALF THE CAPACITY OF THE DEVICE. ADDITIONAL DEVICES MUST BE INSTALLED IF NEW CHANNELS HAVE DEVELOPED.

THE CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION IN WHICH WILL PREVENT TRACK OR FLOW OF MUD ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 1-3" OF STONE, AS CONDITIONS DEMAND. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLE ONTO PUBLIC ROADWAY OR INTO STORM DRAIN MUST BE REMOVED IMMEDIATELY.

CONTRACTOR SHALL INSPECT CONTROL MEASURES AT THE END OF EACH WORKING DAY TO ENSURE MEASURES ARE FUNCTIONING PROPERLY.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION SEDIMENT CONTROL MEASURE SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

FAILURE TO INSTALL, OPERATE, OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN ALL CONSTRUCTION BEING STOPPED ON THE THE JOB UNTIL SUCH MEASURES ARE CORRECTED BACK TO THE APPROVED OR MODIFIED EROSION CONTROL PLANS.

THE SITE CONTRACTOR WILL BE RESPONSIBLE FOR MAINTENANCE OF ALL EROSION CONTROL MEASURES INCLUDING REPLACING OR REPAIRING ANY DAMAGED DEVICES DUE TO ANY CONSTRUCTION ACTIVITY BY OTHERS.

ALL DISTURBED AREAS LEFT MULCHED AFTER 30 DAYS SHALL BE STABILIZED WITH TEMPORARY GRASSING. NO ACTIVITIES SHALL BE CONDUCTED WITHIN THE EXPANDED 25 OR 50-FOOT STREAM BUFFER ALONG THE BANKS OF ALL STATE WATERS.


AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPs WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

AFTER CONSTRUCTION, EROSION AND SEDIMENTATION WILL BE MANAGED BY ONGOING STABILIZATION OF THE PROPERTY BY CONTINUING PROPER MAINTENANCE OF ALL NEW PAVED AREAS, GRASSING, LANDSCAPING AND ANY NEW BUILDINGS OR STRUCTURES.

MINIMIZING WIND EROSION AND CONTROLLING DUST WILL BE ACCOMPLISHED BY ONE OR MORE OF THE FOLLOWING METHODS: COVERING 30% OR MORE OF THE SOIL SURFACE WITH NON-ERODIBLE MATERIAL, ROUGHENING THE SOIL TO PRODUCE RIDGES PERPENDICULAR TO THE PREVAILING WINDS, FREQUENT WATERING OF EXCAVATION AND FILL AREAS. AND/OR PROVIDING GRAVEL OR PAVING AT ENTRANCE/EXIT DRIVES.

CONSTRUCTION MATERIALS WILL BE COVERED WITH TARP TO PROTECT THEM FROM AMBIENT WEATHER CONDITIONS AS NECESSARY

APPROXIMATE ACTIVITY SCHEDULE



APPENDIX B Nephelometric Turbidity Unit (NTU) TABLES

Cold Water (Trout Stream) Surface Water Drainage Area, square miles

		0-4.99	5-9.99	10-24.99	25-49.99	50-99.99	100-249.99	250-499.99	500+	
	1.00-10	25	50	75	150	300	500	500	500	
	10.01-25	25	25	50	75	150	200	500	500	
Site Size,	25.01-50	25	25	25	50	75	100	300	500	
acres	50.01-100	20	25	25	35	59	75	150	300	
	100.01+	20	20	25	25	25	50	60	100	

Warm Water (Supporting Warm Water Fisheries) Surface Water Drainage Area, square miles

			ourrace v	valci Diani	age Aica, s	quai c miles				
		0-4.99	5-9.99	10-24.99	25-49.99	50-99.99	100-249.99	250-499.99	500+	
	1.00-10	7 5	150	200	400	750	750	750	750	
	10.01-25	50	100	100	200	300	500	750	750	
Site Size,	25.01-50	50	50	100	100	200	300	750	750	
acres	50.01-100	50	50	50	100	100	150	300	600	
	100.01+	50	50	50	50	50	100	200	100	

Site Size: 1.7 acres Surface Water Drainage Area: 0.32 square miles NTU value used: 75

CERTIFICATIONS

PROFESSIONAL NO LATER THAN 48 HOURS PRIOR TO THE INSTALLATION OF INITIAL SEDIMENT STORAGE AND PERIMETER CONTROL BMPS.

DESIGN PROFESSIONAL 7-DAY VISIT CERTIFICATION

THE DESIGN PROFESSIONAL WHO PREPARED THE EX&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPs WITHIN 7 DAYS AFTER INSTALLATION. THE PRIMARY PERMITTEE MUST RETAIN THE DESIGN PROFESSIONAL WHO PREPARED THE PLAN, EXCEPT WHEN THE PRIMARY PERMITTEE HAS REQUESTED IN WRITING AND EPD HAS AGREED TO AN ALTERNATE DESIGN PROFESSIONAL, TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPS WHICH THE DESIGN PROFESSIONAL DESIGNED WITHIN SEVEN (7) DAYS AFTER INSTALLATION. THE DESIGN PROFESSIONAL SHALL DETERMINE IF THESE BMPS HAVE BEEN INSTALLED AND ARE BEING MAINTAINED AS SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY DESIGNED. THE DESIGN PROFESSIONAL SHALL REPORT THE RESULTS OF THE INSPECTION TO THE PRIMARY PERMITTEE WITHIN SEVEN (7) DAYS AND THE PERMITTEE MUST CORRECT ALL DEFICIENCIES WITHIN TWO (2) BUSINESS DAYS OF RECEIPT OF THE INSPECTION REPORT FROM THE DESIGN PROFESSIONAL UNLESS WEATHER RELATED SITE CONDITIONS ARE SUCH THAT ADDITIONAL TIME IS REQUIRED.

DATE OF INSPECTION

I CERTIFY THE SITE WAS IN COMPLIANCE WITH THE ES&PC PLAN ON THE DATE OF INSPECTION.

GSWCC LEVEL II DESIGN PROFESSIONAL **CERTIFICATION # 0000073529**

INSPECTIONS REVEALED THE FOLLOWING DISCREPANCIES FROM THE ES&PC PLAN:

THESE DISCREPANCIES MUST BE ADDRESSED IMMEDIATELY AND A RE-INSPECTION SCHEDULED. WORK SHALL NOT PROCEED ON THE SITE UNTIL DESIGN PROFESSIONAL CERTIFICATION IS OBTAINED.

DESIGN PROFESSIONAL'S CERTIFICATION

"I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA," (MANUAL), PUBLISHED BY THE STATE SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED, PROVIDES FOR THE SAMPLING OF THE RECEIVING WATER(S) OR THE SAMPLING OF STORM WATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET REQUIREMENTS CONTAINED IN THE GENERAL NPDES PERMIT NO. GAR 100001."


"I CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A AUTHORIZED AGENT, UNDER MY SUPERVISION.'

WETLAND CERTIFICATION: THE DESIGN PROFESSIONAL, WHOSE SEAL APPEARS HEREON, CERTIFIES THE FOLLOWING: 1) THE NATIONAL WETLAND INVENTORY MAPS HAVE BEEN CONSULTED; AND, 2) THE APPROPRIATE PLAN SHEET [] DOES [] DOES NOT (CIRCLE APPROPRIATE BOX) INDICATE AREAS OF UNITED STATES ARMY CORPS OF ENGINEERS JURISDICTIONAL WETLANDS AS SHOWN ON THE MAPS; AND, 3) IF WETLANDS ARE INDICATED, THE LAND OWNER OR DEVELOPER HAS BEEN ADVISED THAT LAND DISTURBANCE OF PROTECTED WETLANDS SHALL NOT OCCUR UNLESS THE APPROPRIATE FEDERAL WETLANDS ALTERATION ("SECTION 404") PERMIT HAS BEEN OBTAINED.

"I CERTIFY UNDER THE PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT CERTIFIED PERSONAL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED BASED ON MY INQUIRY OF THER PERSON OR PERSONS WHO MANAGE THE SYSTEM. OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION. THE INFORMATION SUBMITTED IS. TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS."

GSWCC LEVEL II DESIGN PROFESSIONAL


CERTIFICATION # 0000073529



DRAINAGE AREA MAP

NOT TO SCALE

NOT TO SCALE





GSWCC LEVEL II CERT. # 0000073529

<u>O</u>

Project No.: 200-01297-1800

B. THE ORDER OF MAJOR LAND DISTURBING ACTIVITIES IS INDICATED IN THE ACTIVITY SCHEDULE LOCATED ON C-504 SHEET.

C. THE TOTAL SITE IS 1.3 ACRES AND 1.3 ACRES OF THE TOTAL IS ESTIMATED TO BE DISTURBED BY EXCAVATION, GRADING OR OTHER ACTIVITIES.

D. DETAILED MAPPING INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER MAJOR GRADING ACTIVITIES, AREA OF SOIL DISTURBANCE, AREAS TO REMAIN UNDISTURBED AND THE LOCATION OF MAJOR STRUCTURAL AND NON-STRUCTURAL CONTROLS, LOCATION OF AREAS WHERE STABILIZATION PRACTICES ARE EXPECTED TO OCCUR, ANY SURFACE WATERS (INCLUDING WETLANDS) AND LOCATIONS WHERE STORM WATER IS TO BE DISCHARGED ARE SHOWN ON ON THE GRADING AND DRAINAGE SHEET OF THESE PLANS.

. THE RECEIVING WATER(S) IS AN UNNAMED TRIBUTARY TO ANTIOCH CREEK. THE EXTENT OF WETLAND ACREAGE AT THE SITE = 0 ACRES

CONTROLS

EROSION AND SEDIMENT CONTROLS:

STABILIZATION MEASURES: ALL DISTURBED AREAS SHALL BE STABILIZED PER THE EROSION CONTROL NOTES INDICATED ON SHEETS CONTAINED WITHIN THIS PLAN SET. ALL TEMPORARY AND PERMANENT MULCHING, FERTILIZING AND SEEDING TO COMPLY WITH THE SCHEDULES SHOWN ON SHEET THIS SHEET AND THE EROSION CONTROL DETAIL SHEET. A RECORD OF THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR, WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE, AND WHEN STABILIZATION MEASURES ARE INITIATED SHALL BE KEPT BY THE CONSTRUCTION SUPERINTENDENT RESPONSIBLE FOR THE OVERALL DEVELOPMENT OF THE SITE.

STRUCTURAL PRACTICES: LOCATION OF ALL PLANNED STRUCTURAL CONTROLS ARE SHOWN ON THE THREE PHASES OF ES&PC PLANS CONTAINED WITHIN THIS PLAN SET. ADDITIONAL STRUCTURAL CONTROLS MAY BE REQUIRED THAT ARE NOT SHOWN AND SHOULD BE UTILIZED WHENEVER APPROPRIATE. ALL STRUCTURAL CONTROLS SHALL BE INSTALLED PER THE REFERENCED SWCC MANUAL AND PER THE DETAILS SHOWN WITHIN THIS PLAN SET.

SEDIMENT BASINS: SEDIMENT BASIN(S) ARE SHOWN ON THE PHASE I AND PHASE II SHEETS OF THE ES&PC PLANS CONTAINED WITHIN THIS PLAN SET. BASIN DETAILS ARE SHOWN ON THE DETAIL SHEETS WITHIN THIS PLAN SET.

DETENTION FACILITIES ARE SHOWN ON THE GRADING AND DRAINAGE PLAN SHEET WITHIN THIS PLAN SET AND ANALYZED IN THE HYDROLOGY STUDY. DRAINAGE IS PROVIDED AND ROUTED FOR AT LEAST A MINIMUM 25 YEAR STORM FREQUENCY.

NON-STORM WATER DISCHARGES

ALL NON-STORM WATER DISCHARGES WILL BE ROUTED THROUGH ON SITE BMPs AND THE STORM WATER MANAGEMENT SYSTEM WHERE POSSIBLE. THESE DISCHARGES INCLUDE FLUSHING OF WATER AND FIRE LINES, IRRIGATION WATER, GROUND WATER DEWATERING OF PITS OR DEPRESSIONS WITHIN THE CONSTRUCTION SITE AND RINSE OFF WATER OF NON-TOXIC MATERIALS

OTHER CONTROLS

WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

WASTE MATERIALS

ALL WASTE MATERIALS WILL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. THE DUMPSTER WILL MEET ALL SOLID WASTE MANAGEMENT REGULATIONS. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED A MINIMUM OF ONCE PER WEEK OR MORE OFTEN IF NECESSARY AND TRASH WILL BE HAULED AS REQUESTED BY LOCAL REGULATIONS, NO CONSTRUCTION WASTE WILL BE BURIED

HAZARDOUS WASTES

ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF THE MANNER SPECIFIED BY LOCAL, STATE AND/OR FEDERAL REGULATIONS AND BY THE MANUFACTURER OF SUCH PRODUCT. THE JOB SITE SUPERINTENDENT, WHO WILL ALSO BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE FOLLOWED. WILL INSTRUCT SITE SUPERINTENDENT, WHO WILL ALSO BE MATERIAL SAFETY DATA SHEETS (MSDS'S) FOR EACH SUBSTANCE WITH HAZARDOUS PROPERTIES THAT IS USED ON THE JOB SITE WILL BE OBTAINED AND USED FOR THE PROPER MANAGEMENT OF POTENTIAL WASTES THAT MAY RESULT FROM THESE PRODUCTS. AN MSDS WILL BE MAINTAINED IN THE ESPCP FILE AT THE JOB SITE CONSTRUCTION TRAILER OFFICE, EACH EMPLOYEE WHO MUST HANDLE A SUBSTANCE WITH HAZARDOUS PROPERTIES WILL BE INSTRUCTED ON THE USE OF MSDS SHEETS AND SPECIFIC INFORMATION IN THE APPLICABLE MSDS FOR THE PRODUCT HE/SHE IS USING. PARTICULARLY REGARDING SPILL CONTROL TECHNIQUES.

THE CONTRACTOR WILL IMPLEMENT THE SPILL PREVENTION CONTROL AND COUNTERMEASURES (SPCC) PLAN FOUND WITHIN THE ESPCP AND WILL TRAIN ALL PERSONAL IN THE PROPER CLEAN UP AND HANDLING OF SPILLED MATERIALS. NO SPILLED HAZARDOUS MATERIAL OF HAZARDOUS WASTE WILL BE ALLOWED TO COME IN CONTACT WITH STORMWATER DISCHARGES. IF SUCH CONTACT OCCUR, THE STORMWATER DISCHARGE WILL BE CONTAINED ON SITE UNTIL APPROPRIATE MEASURES IN COMPLIANCE WITH STATE AND FEDERAL REGULATIONS ARE TAKEN TO DISPOSE OF SUCH CONTAMINATED STORMWATER. IT SHALL BE THE RESPONSIBILITY OF THE JOB SITE SUPERINTENDENT TO PROPERLY TRAIN ALL PERSONNEL IN THE USE OF THE SPCC PLAN.

COMPLIANCE W/ FEDERAL/STATE/LOCAL

REGULATIONS

THE CONTRACTOR WILL OBTAIN COPIES OF ANY AND ALL LOCAL AND STATE REGULATIONS THAT ARE APPLICABLE TO STORM WATER MANAGEMENT, EROSION CONTROL, AND POLLUTION MINIMIZATION AT THIS JOB SITE AND WILL COMPLY FULLY WITH SUCH REGULATIONS. THE CONTRACTOR WILL SUBMIT WRITTEN EVIDENCE OF SUCH COMPLIANCE IF REQUESTED BY THE OWNER OR ANY AGENT OF A REGULATORY BODY. THE CONTRACTOR WILL COMPLY WITH ALL CONDITIONS OF ANY AND ALL LOCAL, STATE, AND FEDERAL AGENCIES WHICH HAVE GOVERNING AUTHORITY: INCLUDING THE CONDITIONS RELATED TO MAINTAINING THE ESPCP AND EVIDENCE OF COMPLIANCE WITH ESPCP AT THE JOB SITE ALLOWING REGULATORY PERSONNEL ACCESS TO THE JOB SITE AND TO RECORDS IN ORDER TO DETERMINE COMPLIANCE.

SANITARY WASTES

A MINIMUM OF ONE PORTABLE SANITARY UNIT WILL PROVIDED FOR EVERY TEN (10) WORKERS ON THE SITE. ALL SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF ONE TIME PER WEEK BE LICENSED PORTABLE FACILITY PROVIDER IN COMPLETE COMPLIANCE WITH LOCAL AND STATE REGULATIONS.

ALL SANITARY WASTE UNITS WILL BE LOCATED IN AN AREA WHERE THE LIKELIHOOD OF THE UNIT CONTRIBUTING TO THE STORM WATER DISCHARGES IS NEGLIGIBLE. ADDITIONAL CONTAINMENT BMP'S MUST BE IMPLEMENTED, SUCH AS GRAVEL BAGS OR SPECIALLY DESIGNED PLASTIC SKID CONTAINERS AROUND THE BASE, TO PREVENT WASTES FROM TO CONTRIBUTING THE STORM WATER DISCHARGES. THE LOCATION OF SANITARY WASTE UNITS MUST BE IDENTIFIED ON THE ES&PC PLAN PHASE II SHEET WITHIN THIS PLAN SET BY THE CONTRACTOR ONCE THE LOCATION

INVENTORY FOR POLLUTION PREVENTION PLAN

THE FOLLOWING MATERIALS ARE EXPECTED ONSITE DURING CONSTRUCTION: CONCRETE PRODUCTS, ASPHALT, PETROLEUM BASED FUELS AND LUBRICANTS FOR EQUIPMENT, TAR, METAL BUILDING MATERIALS, LUMBER, SHEET ROCK, FLOOR COVERINGS, ELECTRICAL WIRE AND FIXTURES, PAINTS/STAINS/FINISHING TREATMENTS, POINTS, POINTS SOLVENTS, ADDITIVES FOR SOIL STABILIZATION, CLEANING SOLVENTS, PESTICIDES, FERTILIZERS, HERBICIDES, CRUSHED STONE, PLASTIC AND METAL PIPES.

SPILL PREVENTION

PRACTICES SUCH AS GOOD HOUSEKEEPING, PROPER HANDLING OF HAZARDOUS PRODUCTS AND PROPER SPILL CONTROL PRACTICES WILL BE FOLLOWED TO REDUCE THE RISK OF SPILLS AND SUBSEQUENT DISCHARGE INTO STORM WATER

GOOD HOUSEKEEPING

1. QUANTITIES OF PRODUCTS STORED ONSITE WILL BE LIMITED TO THE AMOUNT NEEDED FOR THE JOB.

2. PRODUCTS AND MATERIALS WILL BE STORED IN THE NEAT, ORDERLY MANNER IN APPROPRIATE CONTAINERS PROTECTED FROM RAINFALL, WHERE POSSIBLE. 3. PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH MANUFACTURER LABELS LEGIBLE AND VISIBLE

4. PRODUCT MIXING AND DISPOSAL OF PRODUCT CONTAINERS WILL BE ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

5. THE CONTRACTOR WILL INSPECT SUCH MATERIALS TO ENSURE PROPER USE, STORAGE AND DISPOSAL.

PRODUCT SPECIFIC PRACTICES

PETROLEUM BASED PRODUCTS - CONTAINERS FOR PRODUCTS SUCH AS FUELS, LUBRICANTS AND TARS WILL INSPECTED DAILY FOR LEAKS AND SPILLS. THIS INCLUDES ON-SITE VEHICLE AND MACHINERY DAILY INSPECTIONS AND REGULAR PREVENTATIVE MAINTENANCE OF SUCH EQUIPMENT. EQUIPMENT MAINTENANCE AREAS WILL BE LOCATED AWAY FROM STATE WATERS, NATURAL DRAINS AND STORM WATER DRAINAGE INLETS. IN ADDITION, TEMPORARY FUELING TANKS SHALL HAVE A SECONDARY CONTAINMENT LINER TO PREVENT/MINIMIZE SITE CONTAMINATION. DISCHARGE OF OILS, FUELS AND LUBRICANTS IS PROHIBITED PROPER DISPOSAL METHODS WILL INCLUDE IN A SUITABLE CONTAINER AND DISPOSAL AS REQUIRED BE LOCAL AND STATE REGULATIONS.

PAINTS/FINISHES/SOLVENTS - ALL PRODUCTS WILL BE STORED IN TIGHTLY SEALED ORIGINAL CONTAINERS WHEN NOT IN USE. EXCESS PRODUCT AND MATERIALS USED WITH THESE PRODUCTS WILL NOT BE DISCHARGED TO THE STORM WATER COLLECTION SYSTEM. EXCESS PRODUCT, MATERIALS USED WITH THESE PRODUCTS AND PRODUCT CONTAINERS WILL BE DISPOSED OF ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.

CONCRETE TRUCK WASHING - CLEANSING PRODUCTS WILL BE APPLIED AT RATES THAT DO NOT EXCEED THE MANUFACTURES' SPECIFICATIONS OR ABOVE THE GUIDELINES SET. ANY STORAGE OF THESE MATERIALS WILL BE UNDER ROOF IN SEALED CONTAINERS.

BUILDING MATERIALS - NO BUILDING OR CONSTRUCTION MATERIALS WILL BE BURIED OR DISPOSED OF ONSITE. ALL SUCH MATERIAL WILL BE DISPOSED OF IN PROPER WASTE DISPOSAL PROCEDURES.

SPILL CLEANUP AND CONTROL PRACTICES

1. LOCAL, STATE AND MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND PROCEDURES WILL BE MADE AVAILABLE

2. MATERIAL AND FOUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS. TYPICAL MATERIALS AND EQUIPMENT INCLUDES, BUT IS NOT LIMITED TO, BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, CAT LITTER, SAND, SAWDUST, AND PROPERLY LABELED PLASTIC AND METAL WASTE CONTAINERS.

3. SPILL PREVENTION PRACTICES AND PROCEDURES WILL BE REVIEWED AFTER A SPILL AND ADJUSTED AS NECESSARY TO PREVENT FUTURE SPILLS.

4. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. ALL SPILLS WILL BE REPORTED AS REQUIRED BY LOCAL, STATE AND FEDERAL REGULATIONS. 5. FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN IN SURFACE WATER). THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITH IN 24 HOURS AT 1-800-426-2675.

6. FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE GEORGIA EPD WILL BE CONTACTED WITHIN 24 HOURS. 7. FOR SPILLS LESS THEN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE

SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS

THE CONTRACTOR SHALL NOTIFY THE LICENSED PROFESSIONAL WHO PREPARED THIS PLAN IF MORE THAN 1320 GALLONS OF PETROLEUM IS STORED ONSITE (THI INCLUDES CAPACITIES OF EQUIPMENT) OR IF ANY ONE PIECE OF EQUIPMENT HAS A COUNTERMEASURES PLAN PREPARED BY LICENSED PROFESSIONAL.

OFFSITE VEHICLE TRACKING

A STABILIZED CONSTRUCTION EXIT HAS BEEN PROVIDED TO HELP REDUCE TRACKING OF SEDIMENT. SEE EROSION CONTROL PLANS AND DETAIL FOR CONSTRUCTION EXIT LOCATION AND CONSTRUCTION DETAILS. ANY PAVED STREET ADJACENT TO THE SITE CONSTRUCTION EXIT WILL BE COVERED WITH A TARPAULIN OR A WASH DOWN STATION UTILIZED AS APPROPRIATE FOR THE LEVEL OF SEDIMENT PRESENT.

24 HOUR CONTACT: MR. PHILIP MALLON 770-313-9855

INSPECTIONS

A. PERMITEE REQUIREMENTS:

1. EACH DAY WHEN ANY TYPE OF CONSTRUCTION ACTIVITY HAS TAKEN PLACE AT A PRIMARY PERMITTEE'S SITE, CERTIFIED PERSONNEL PROVIDED BY THE PRIMARY PERMITTEE SHALL INSPECT: (A) ALL AREAS AT THE PRIMARY PERMITTEE'S SITE WHERE PETROLEUM PRODUCTS ARE STORED, USED, OR HANDLED FOR SPILLS AND LEAKS FROM VEHICLES AND EQUIPMENT AND (B) ALL LOCATIONS AT THE PRIMARY PERMITTEE'S SITE WHERE VEHICLES ENTER OR EXIT THE SITE FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING. THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED.

2. MEASURE AND RECORD RAINFALL WITHIN DISTURBED AREAS OF THE SITE

PURPOSE OF COMPLIANCE WITH THIS PERMIT SHALL BE REPRESENTATIVE

THAT HAVE NOTE MET FINAL STABILIZATION ONCE EVERY 24 HOURS

NON-WORKING FEDERAL HOLIDAY. THE DATA COLLECTED FOR THE

EXCEPT ANY NON-WORKING SATURDAY, NON-WORKING SUNDAY AND

OF THE MONITORED ACTIVITY. MEASUREMENT OF RAINFALL MAY BE SUSPENDED IF ALL AREAS OF THE SITE HAVE UNDERGONE FINAL STABILIZATION OR ESTABLISHED A CROP OF ANNUAL VEGETATION AND A SEEDING OF TARGET PERENNIALS APPROPRIATE FOR THE REGION. 3. CERTIFIED PERSONNEL (PROVIDED BY THE PRIMARY PERMITTEE) SHALL INSPECT THE FOLLOWING AT LEAST ONCE EVERY FOURTEEN (14) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.5 INCHES RAINFALL OR GREATER (UNLESS SUCH STORM ENDS AFTER 5:00 PM ON ANY FRIDAY OR ON ANY NON-WORKING SATURDAY, NON-WORKING SUNDAY OR ANY NON-WORKING FEDERAL HOLIDAY IN WHICH CASE THE INSPECTION SHALL BE COMPLETED BY THE END OF THE NEXT BUSINESS DAY AND/OR WORKING DAY, WHICHEVER OCCURS FIRST): (A) DISTURBED AREAS OF THE PRIMARY PERMITTEE'S CONSTRUCTION SITE; (B) AREAS USED BY THE PRIMARY PERMITTEE FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION; AND (C) STRUCTURAL CONTROL MEASURES. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN APPLICABLE TO THE PRIMARY PERMITTEE'S SITE SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN

IV.D.4.A.(4). THESE INSPECTIONS MUST BE CONDUCTED UNTIL A NOTICE OF TERMINATION IS SUBMITTED. 4. CERTIFIED PERSONNEL (PROVIDED BY THE PRIMARY PERMITTEE) SHALL INSPECT AT LEAST ONCE PER MONTH DURING THE TERM OF THIS PERMIT (I.E., UNTIL A NOTICE OF TERMINATION IS RECEIVED BY EPD) THE AREAS OF THE SITE THAT HAVE UNDERGONE FINAL STABILIZATION OR ESTABLISHED A CROP OF ANNUAL VEGETATION AND A SEEDING OF TARGET PERENNIALS APPROPRIATE FOR THE REGION. THESE AREAS SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM AND THE RECEIVING WATER(S). EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE

PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATER(S). FOR AREAS

OF A SITE THAT HAVE UNDERGONE FINAL STABILIZATION OR ESTABLISHED

A CROP OF ANNUAL VEGETATION AND A SEEDING OF TARGET PERENNIALS

APPROPRIATE FOR THE REGION, THE PERMITTEE MUST COMPLY WITH PART

EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATER(S). 5. BASED ON THE RESULTS OF EACH INSPECTION, THE SITE DESCRIPTION AND THE POLLUTION PREVENTION AND CONTROL MEASURES IDENTIFIED IN THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN, THE PLAN SHALL BE REVISED AS APPROPRIATE NOT LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION. IMPLEMENTATION OF SUCH CHANGES SHALL BE MADE AS SOON AS PRACTICAL BUT IN NO CASE LATER THAN SEVEN (7) CALENDAR DAYS FOLLOWING EACH INSPECTION.

INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE

6. A REPORT OF EACH INSPECTION THAT INCLUDES THE NAME(S) OF CERTIFIED PERSONNEL MAKING EACH INSPECTION, THE DATE(S) OF EACH INSPECTION, CONSTRUCTION PHASE (I.E., INITIAL, INTERMEDIATE OR FINAL), MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN, AND ACTIONS TAKEN IN ACCORDANCE WITH PART IV.D.4.A.(5). OF THE PERMIT SHALL BE MADE AND RETAINED AT THE SITE OR BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION UNTIL THE ENTIRE SITE OR THAT PORTION OF A CONSTRUCTION PROJECT THAT HAS BEEN PHASED HAS UNDERGONE FINAL STABILIZATION AND A NOTICE OF TERMINATION IS SUBMITTED TO EPD. SUCH REPORTS SHALL BE READILY AVAILABLE BY END OF THE SECOND BUSINESS DAY AND/OR WORKING DAY AND SHALL IDENTIFY ALL INCIDENTS OF BEST MANAGEMENT PRACTICES THAT HAVE NOT BEEN PROPERLY INSTALLED AND/OR MAINTAINED AS DESCRIBED IN THE PLAN. WHERE THE REPORT DOES NOT IDENTIFY ANY INCIDENTS, THE INSPECTION REPORT SHALL CONTAIN A CERTIFICATION THAT THE BEST MANAGEMENT PRACTICES ARE IN COMPLIANCE WITH THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN. THE REPORT SHALL BE SIGNED IN ACCORDANCE WITH PART V.G.2. OF THIS PERMIT.

REPORTING

1. THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTION SITE OR THE RECORDS SHALL BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS A NOT IS SUBMITTED IN ACCORDANCE

2. ALL SAMPLING REPORTS SHALL INCLUDE THE FOLLOWING INFORMATION: a. THE RAINFALL AMOUNT, DATE, EXACT PLACE AND TIME OF SAMPLING OR

MEASUREMENTS: b. THE NAME(S) OF THE CERTIFIED PERSONNEL WHO PERFORMED THE

SAMPLING AND MEASUREMENTS:

c. THE DATE(S) ANALYSES WERE PERFORMED;

d. THE TIME(S) ANALYSES WERE INITIATED;

e. THE NAME(S) OF THE CERTIFIED PERSONNEL WHO PERFORMED THE

ANALYSES; f. REFERENCES AND WRITTEN PROCEDURES, WHEN AVAILABLE, FOR THE ANALYTICAL TECHNIQUES OR METHODS USED;

g. THE RESULTS OF SUCH ANALYSES, INCLUDING THE BENCH SHEETS, INSTRUMENT READOUTS, COMPUTER DISKS OR TAPES, ETC., USED TO DETERMINE THESE RESULTS;

h. RESULTS WHICH EXCEED 1000 NTU SHALL BE REPORTED AS "EXCEEDS 100

i. CERTIFICATION STATEMENT THAT SAMPLING WAS CONDUCTED AS PER THE PLAN.

3. ALL WRITTEN CORRESPONDENCE REQUIRED BY THIS PERMIT SHALL BE SUBMITTED BY RETURN RECEIPT CERTIFIED MAIL (OR SIMILAR SERVICE) TO THE APPROPRIATE DISTRICT OFFICE OF THE EPD ACCORDING TO THE SCHEDULE IN APPENDIX A OF THIS PERMIT. THE PERMITTEE SHALL RETAIN A COPY OF THE PROOF OF SUBMITTAL AT THE CONSTRUCTION SITE OR THE PROOF OF SUBMITTAL SHALL BE READILY AVAILABLE AT A DESIGNATED LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTIL SUCH TIME AS A NOT IS SUBMITTED IN ACCORDANCE WITH PART VI. IF AN ELECTRONIC SUBMITTAL IS PROVIDED BY EPD THEN THE WRITTEN CORRESPONDENCE MAY BE SUBMITTED ELECTRONICALLY; IF REQUIRED, A PAPER COPY MUST ALSO BE SUBMITTED BY RETURN RECEIPT CERTIFIED MAIL OR SIMILAR SERVICE.

MAINTENANCE

THE PLAN SHALL INCLUDE A DESCRIPTION OF PROCEDURES TO ENSURE THE TIMELY MAINTENANCE OF VEGETATION, EROSION AND SEDIMENT CONTROL MEASURES AND OTHER PROTECTIVE MEASURES IDENTIFIED IN THE SITE PLAN.

SAMPLING FREQUENCY

D. SAMPLING FREQUENCY:

 THE PRIMARY PERMITTEE MUST SAMPLE IN ACCORDANCE WITH THE PLAN AT LEAST ONCE FOR EACH RAINFALL EVENT DESCRIBED BELOW. FOR A QUALIFYING EVENT, THE PERMITTEE SHALL SAMPLE AT THE BEGINNING OF ANY STORM WATER DISCHARGE TO A MONITORED RECEIVING WATER AND/OR FROM A MONITORED OUTFALL LOCATION WITHIN FORTY-FIVE (45) MINUTES OR AS SOON AS POSSIBLE.

2. HOWEVER, WHERE MANUAL AND AUTOMATIC SAMPLING ARE IMPOSSIBLE (AS DEFINED IN THIS PERMIT), OR ARE BEYOND THE PERMITTEE'S CONTROL, THE PERMITTEE SHALL TAKE SAMPLES AS SOON AS POSSIBLE, BUT IN NO CASE MORE THAN TWELVE (12) HOURS AFTER THE BEGINNING OF THE STORM WATER DISCHARGE.

3. SAMPLING BY THE PERMITTEE SHALL OCCUR FOR THE FOLLOWING QUALIFYING EVENTS:

a. FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR FROM AN OUTFALL, THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH WITH A STORM WATER DISCHARGE THAT OCCURS DURING NORMAL BUSINESS HOURS AS DEFINED IN THIS PERMIT AFTER ALL CLEARING AND GRUBBING OPERATIONS HAVE BEEN COMPLETED, BUT PRIOR TO COMPLETION OF MASS GRADING OPERATIONS, IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE SAMPLING LOCATION;

b. IN ADDITION TO (A) ABOVE, FOR EACH AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR FROM AN OUTFALL, THE FIRST RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH WITH A STORM WATER DISCHARGE THAT OCCURS DURING NORMAL BUSINESS HOURS AS DEFINED IN THIS PERMIT EITHER 90 DAYS AFTER THE FIRST SAMPLING EVENT OR AFTER ALL MASS GRADING OPERATIONS HAVE BEEN COMPLETED, BUT PRIOR TO SUBMITTAL OF A NOT, IN THE DRAINAGE AREA OF THE LOCATION SELECTED AS THE SAMPLING LOCATION, WHICHEVER

c. AT THE TIME OF SAMPLING PERFORMED PURSUANT TO (A) AND (B) ABOVE, IF BMPS IN ANY AREA OF THE SITE THAT DISCHARGES TO A RECEIVING WATER OR FROM AN OUTFALL ARE NOT PROPERLY DESIGNED, INSTALLED AND MAINTAINED, CORRECTIVE ACTION SHALL BE DEFINED AND IMPLEMENTED WITHIN TWO (2) BUSINESS DAYS, AND TURBIDITY SAMPLES SHALL BE TAKEN FROM DISCHARGES FROM THAT AREA OF THE SITE FOR EACH SUBSEQUENT RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH DURING NORMAL BUSINESS HOURS* UNTIL THE SELECTED TURBIDITY STANDARD IS ATTAINED, OR UNTIL POST-STORM EVENT INSPECTIONS DETERMINE THAT BMPS ARE PROPERLY DESIGNED, INSTALLED AND

d. WHERE SAMPLING PURSUANT TO (A), (B) OR (C) ABOVE IS REQUIRED BUT NOT POSSIBLE (OR NOT REQUIRED BECAUSE THERE WAS NO DISCHARGE) THE PERMITTEE, IN ACCORDANCE WITH PART IV.D.4.a.(6), MUST INCLUDE A WRITTEN JUSTIFICATION IN THE INSPECTION REPORT OF WHY SAMPLING WAS NOT PERFORMED. PROVIDING THIS JUSTIFICATION DOES NOT RELIEVE THE PERMITTEE OF ANY SUBSEQUENT SAMPLING OBLIGATIONS UNDER (A), (B) OR (C) ABOVE; AND

 EXISTING CONSTRUCTION ACTIVITIES, I.E., THOSE THAT ARE OCCURRING ON OR BEFORE THE EFFECTIVE DATE OF THIS PERMIT, THAT HAVE MET THE SAMPLING REQUIRED BY (A) ABOVE SHALL SAMPLE IN ACCORDANCE WITH (B). THOSE EXISTING CONSTRUCTION ACTIVITIES THAT HAVE MET THE SAMPLING REQUIRED BY (B) ABOVE SHALL NOT BE REQUIRED TO CONDUCT ADDITIONAL SAMPLING OTHER THAN AS REQUIRED BY (C)

*NOTE THAT THE PERMITTEE MAY CHOOSE TO MEET THE REQUIREMENTS OF a. AND b. ABOVE BY COLLECTING TURBIDITY SAMPLES FROM ANY RAIN EVENT THAT REACHES OR EXCEEDS 0.5 INCH AND ALLOWS FOR SAMPLING AT ANY TIME OF THE DAY OR WEEK.

RETENTION OF RECORDS

1. THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTIN SITE OR THE RECORDS SHALL BE READILY AVAILABLE AT A DESIGNATED ALTERNATE LOCATION FROM COMMENCEMENT OF CONSTRUCTION UNTILL SUCH TIME AS A NOT IS SUMITTED IN ACCORDANCE WITH PART VI:

a. A COPY OF ALL NOTICES OF INTENT SUBMITTED TO EPD;

b. A COPY OF THE EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN REQUIRED BY THIS PERMIT;

c. THE DESIGN PROFESSIONAL'S REPORT OF THE RESULTS OF THE INSPECTION CONDUCTED IN ACCORDANCE WITH PART IV.A.5. OF THIS

d. A COPY OF ALL SAMPLING INFORMATION, RESULTS, AND REPORTS REQUIRED BY THIS PERMIT:

e. A COPY OF ALL INSPECTION REPORTS GENERATED IN ACCORDANCE WITH PART IV.D.4.a. OF THIS PERMIT; f. A COPY OF ALL VIOLATION SUMMARIES AND VIOLATION SUMMARY

REPORTS GENERATED IN ACCORDANCE WITH PART III.D.2. OF THIS PERMIT;

g. DAILY RAINFALL INFORMATION COLLECTED IN ACCORDANE WITH PART IV.D.4.A.2. OF THIS PERMIT.

2. COPIES OF ALL NOTICES OF INTENT, NOTICES OF TERMINATION, INSPECTION REPORTS, SAMPLING REPORTS (INCLUDING ALL CALIBRATION AND MAINTENANCE RECORDS AND ALL ORIGINAL STRIP CHART RECORDINGS FOR CONTINUOUS MONITORING INSTRUMENTATION) OR OTHER REPORTS REQUESTED BY THE EPD, EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS, RECORDS OF ALL DATA USED TO COMPLETE THE NOTICE OF INTENT TO BE COVERED BY THIS PERMIT AND ALL OTHER RECORDS REQUIRED BY THIS PERMIT SHALL BE RETAINED BY THE PERMITTEE WHO EITHER PRODUCED OR USED IT FOR A PERIOD OF AT LEAST THREE YEARS FROM THE DATE THAT THE NOT IS SUBMITTED IN ACCORDANCE WITH PART VI. OF THIS PERMIT. THESE RECORDS MUST BE MAINTAINED AT THE PERMITTEE'S PRIMARY PLACE OF BUSINESS OR AT A DESIGNATED ALTERNATIVE LOCATION ONCE THE CONSTRUCTION ACTIVITY HAS CEASED AT THE PERMITTED SITE. THIS PERIOD MAY BE EXTENDED BY REQUEST OF THE EPD AT ANY TIME UPON WRITTEN NOTIFICATION TO THE PERMITTEE.





<u>N</u> S

hecked By:

Project No.: 200-01297-1800

Designed By:

Drawn By:

Custom Soil Resource Report

PRIMARY PERMITTEE TO BE PROVIDED AFTER PROJECT IS AWARDED.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI	
СеВ	Cecil sandy loam, 2 to 6 percent slopes	5.7	15.9%	
MdB	Madison sandy loam, 2 to 6 percent slopes	1.8	5.0%	
MdC	Madison sandy loam, 6 to 10 1.0 percent slopes			
MfE2	Madison sandy clay loam, 10 to 25 percent slopes, eroded	7.3	20.3%	
PaC	Pacolet sandy loam, 6 to 10 percent slopes	6.7	18.7%	
PaE	Pacolet sandy loam, 10 to 25 percent slopes	4.1	11.3%	
WH	Wehadkee soils, 0 to 2 percent slopes, frequently flooded	9.4	26.1%	
Totals for Area of Interest		36.0	100.0%	

GSWCC LEVEL II CERT. # 0000073529

CHECKLIS

esigned By