



- AS-BUILT REQUIRED PRIOR TO FINAL BUILDING INSPECTION
- THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES SHALL OCCUR PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES.
- THE ONLY MATERIAL TO BE BURIED ON-SITE IS VEGETATIVE MATERIAL, PROVIDED IT IS NOT BURIED WITHIN 100' OF ANY PROPERTY LINE OR ENCLOSED STRUCTURE. CONSTRUCTION WASTE MAY NEITHER BE BURNED NOR BURIED AND MUST BE TAKEN TO A STATE APPROVED LANDFILL.
- ALL WORK SHALL COMPLY WITH APPLICABLE STATE, FEDERAL AND LOCAL CODES.
- ALL MATERIALS AND CONSTRUCTION METHODS TO BE IN ACCORDANCE WITH THE FAYETTE COUNTY STANDARDS AND THE GEORGIA DEPARTMENT OF TRANSPORTATION, AS APPLICABLE.
- DEVIATION FROM THESE PLANS AND SPECIFICATIONS WITHOUT THE PRIOR WRITTEN CONSENT OF THE ENGINEER MAY CAUSE THE WORK TO BE UNACCEPTABLE.
- CONTRACTOR IS RESPONSIBLE FOR NOTIFICATIONS AND LIAISON WITH UTILITY COMPANIES IN THE PROCESS OF LOCATING, RELOCATION AND TIE-IN TO PUBLIC UTILITIES. ALSO, CONTRACTOR IS RESPONSIBLE FOR NOTIFYING ALL INSPECTORS, INCLUDING COUNTY AND CITY INSPECTORS PRIOR TO BEGINNING SITE CONSTRUCTION.
- THERE MAY BE ADDITIONAL UTILITIES THAN THOSE SHOWN ON THESE PLANS. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR LOCATIONS SHOWN AND IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATIONS AND NECESSARY INVERTS OF ALL UTILITIES WITHIN THE LIMITS OF CONSTRUCTION. PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE APPROPRIATE DEPARTMENT OF THE UTILITY COMPANIES. THE CONTRACTOR IS RESPONSIBLE FOR THE NOTIFICATIONS AND LIAISON WITH UTILITY COMPANIES IN THE PROCESS OF LOCATING, RELOCATING AND TIE-IN TO THE PUBLIC UTILITIES.
- IF CONTRACTOR DAMAGES ANY EXISTING UTILITIES DURING CONSTRUCTION, HE SHALL, AT HIS OWN EXPENSE, REPLACE OR REPAIR THE UTILITIES TO ORIGINAL CONDITION AND QUALITY, AS APPROVED BY THE ENGINEER AND REPRESENTATIVE OF THE APPROPRIATE UTILITY COMPANY.
- LAND DISTURBANCE PERMIT TO BE DISPLAYED ON SITE AT ALL TIMES DURING CONSTRUCTION.
- CONSTRUCTION EQUIPMENT SHALL NOT BE PARKED IN RIGHT-OF-WAY AND MUST BE STORED WITHIN SITE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING A MARKED-UP SET OF DESIGN DRAWINGS SHOWING ALL "AS-BUILT" CONDITIONS. THESE "RECORD DRAWINGS" SHALL BE MADE AVAILABLE TO THE DESIGNER AND/OR THE COUNTY INSPECTOR UPON REQUEST. THE MARK-UPS SHALL BE AT THE SITE AT ALL TIMES AND SHALL BE UTILIZED BY THE CONTRACTOR TO DEVELOP FINAL RECORD DRAWINGS.
- STUMPS AND CONSTRUCTION DEBRIS SHALL BE DEPOSITED IN A PROPERLY PERMITTED LANDFILL.
- THIS PROPERTY IS NOT LOCATED IN A 100 YEAR FLOOD HAZARD AREA BASED ON THE FLOOD INSURANCE RATE MAP FOR THIS AREA. THE MAP NUMBER FOR THIS AREA IS 13113C0107E, AND THE DATE OF SAID MAP IS SEPTEMBER 26, 2008. THIS DETERMINATION WAS MADE BY GRAPHICALLY DETERMINING THE POSITION OF THIS SITE ON SAID FIRM MAP UNLESS NOTED OTHERWISE.
- THE CONTRACTOR SHALL TELEPHONE TOLL FREE 1-800-282-7411 A MINIMUM OF 48 HOURS PRIOR TO THE START OF ANY EXCAVATION AS SHOWN AND NOTED ON THE PLANS FOR A UTILITY LOCATION SERVICE.
- ALL APPROPRIATE SITE WORK SHALL CONFORM TO ADA STANDARDS.

APPROVAL REVIEW STAMPS

LOCATION MAP (NTS)



FEMA MAP



FEMA STATEMENT

THIS PROPERTY IS NOT LOCATED IN A 100 YEAR FLOOD HAZARD AREA BASED ON THE FLOOD INSURANCE RATE MAP FOR THIS AREA. THE MAP NUMBER FOR THIS AREA IS 13113C0107E AND THE DATE OF SAID MAP IS SEPTEMBER 26, 2008.

REQUIRED ENGINEER'S INSPECTION

AS PER THE GEORGIA DEPARTMENT OF NATURAL RESOURCES ENVIRONMENTAL PROTECTION DIVISION, NPDES GENERAL PERMITS FOR CONSTRUCTION ACTIVITY GARY0001, GARY0002, & GARY0003, PART IV, A., 7 REQUIRES THE EROSION CONTROL PLAN DESIGN PROFESSIONAL TO MAKE A SITE INSPECTION. FOR STAND ALONE PROJECTS THAT BEGIN CONSTRUCTION ACTIVITY AFTER THE EFFECTIVE DATE OF THIS PERMIT, THE PRIMARY PERMITEE MUST RETAIN THE DESIGN PROFESSIONAL WHO PREPARED THE EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN, EXCEPT WHEN THE PRIMARY PERMITEE HAS REQUESTED IN WRITING AND EPD HAS AGREED TO AN ALTERNATE DESIGN PROFESSIONAL, TO INSPECT THE INSTALLATION OF THE CONTROL MEASURES (BMP'S) WHICH THE DESIGN PROFESSIONAL DESIGNED WITHIN SEVEN (7) DAYS AFTER THE INITIAL CONSTRUCTION ACTIVITIES COMMENCE. FOR CONSTRUCTION ACTIVITIES WHERE CONSTRUCTION BEGAN ON OR BEFORE THE EFFECTIVE DATE OF THIS PERMIT, THE INSPECTION IS TO OCCUR WITHIN SEVEN (7) DAYS AFTER THE PLAN HAS BEEN IMPLEMENTED. THE DESIGN PROFESSIONAL SHALL DETERMINE IF THESE BMP'S HAVE BEEN INSTALLED AND ARE BEING MAINTAINED AS DESIGNED. THE DESIGN PROFESSIONAL SHALL REPORT THE RESULTS OF THE INSPECTION TO THE PRIMARY PERMITEE WITHIN SEVEN (7) DAYS AND THE PERMITEE MUST CORRECT ALL DEFICIENCIES WITHIN TWO (2) BUSINESS DAYS OF RECEIPT OF THE INSPECTION REPORT FROM THE DESIGN PROFESSIONAL UNLESS WEATHER RELATED SITE CONDITIONS ARE SUCH THAT ADDITIONAL TIME IS REQUIRED



Contact 811 before you dig.

24 HOUR CONTACT:
BARRY BABB
TEL: (770)- 706-4800

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY


ADDRESS: 340 HEWELL ROAD
JONESBORO, GA 30238
LAND LOTS 172 OF THE 5TH DISTRICT
FAYETTE COUNTY, GEORGIA

TOTAL AREA: 51 ACRES
DISTURBED AREA: 38.29 ACRES

OWNER:

NAME: FAYETTE COUNTY
ADDRESS: 155 JOHNSON AVENUE
FAYETTEVILLE, GA 30214
CONTACT: BARRY BABB
PHONE: (770)- 706-4800


SHEET INDEX				
SHEET	DRAWING NAME	SHEET NAME	PLAN DATE	LAST REVISED
1	C-000	COVER SHEET	04/01/2022	09/26/2023
2	C-100	EXISTING CONDITIONS AND DEMOLITION PLAN	04/01/2022	05/31/2023
3	C-200	OVERALL SITE AND UTILITY PLAN	04/01/2022	05/31/2023
4	C-201	SITE AND UTILITY PLAN	04/01/2022	05/31/2023
5	C-202	SITE AND UTILITY PLAN	04/01/2022	05/31/2023
6	C-203	SITE AND UTILITY PLAN	04/01/2022	05/31/2023
7	C-204	ROADWAY PROFILE	04/01/2022	05/31/2023
8	C-205	ROADWAY PROFILE	04/01/2022	05/31/2023
9	C-206	ROADWAY PROFILE	04/01/2022	05/31/2023
10	C-207	ROADWAY PROFILE	04/01/2022	05/31/2023
11	C-208	ROADWAY PROFILE	04/01/2022	05/31/2023
12	C-209	ROADWAY PROFILE	04/01/2022	05/31/2023
13	C-210	ROADWAY PROFILE	04/01/2022	05/31/2023
14	C-211	ROADWAY PROFILE	04/01/2022	05/31/2023
15	C-212	ROADWAY PROFILE	04/01/2022	05/31/2023
16	C-213	ROADWAY PROFILE	04/01/2022	05/31/2023
17	C-214	TYPICALS	04/01/2022	05/31/2023
18	C-300	GRADING AND DRAINAGE PLAN	04/01/2022	05/31/2023
19	C-301	GRADING AND DRAINAGE PLAN	04/01/2022	05/31/2023
20	C-302	GRADING AND DRAINAGE PLAN	04/01/2022	05/31/2023
21	C-400	STORM PROFILES	04/01/2022	05/31/2023
22	C-401	STORM PROFILES	04/01/2022	05/31/2023
23	C-402	STORM PROFILES	04/01/2022	05/31/2023
24	C-403	STORMWATER MANAGEMENT SHEET	04/01/2022	05/31/2023
25	C-404	STORMWATER MANAGEMENT DATA	04/01/2022	05/31/2023
26	GA-P	GA POWER EASEMENT EXHIBIT	04/01/2022	05/31/2023
27	GA-P-1	GA POWER EASEMENT EXHIBIT PROFILE	04/01/2022	05/31/2023
28	C-501	CONSTRUCTION DETAILS	04/01/2022	05/31/2023
29	C-502	CONSTRUCTION DETAILS	04/01/2022	05/31/2023
30	ER-000	EROSION CONTROL COVER SHEET	04/01/2022	09/26/2023
31	ER-100	EROSION CONTROL NOTES	04/01/2022	05/31/2023
32	ER-200	EROSION CONTROL PLAN - INITIAL PHASE	04/01/2022	05/31/2023
33	ER-300	EROSION CONTROL PLAN - INTERMEDIATE PHASE	04/01/2022	05/31/2023
34	ER-400	EROSION CONTROL PLAN - FINAL PHASE	04/01/2022	05/31/2023
35	ER-500	EROSION CONTROL DETAILS	04/01/2022	05/31/2023
36	ER-501	EROSION CONTROL DETAILS	04/01/2022	05/31/2023



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

NO.	REVISION REFERENCE	DATE
03	EROSION APPENDIX 1	09/26/2023
02	VIEWPORT REVISIONS	11/22/2022
01	ACCESS ROAD REDESIGN	08/19/2022




GSWCC CERT #78081

SHEET TITLE
COVER SHEET

DRAWN BY ORG	CHECKED BY SMM
SCALE N/A	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
DRAWING NUMBER

C-000
SHEET 1 of 37




**EXISTING CONDITIONS/
DEMOLITION NOTES**

1. THIS PROPERTY MAY BE SUBJECT TO EASEMENTS, CLAIMS, PRESCRIPTIONS, SUBSURFACE CONDITIONS, OR OTHER MATTERS OF TITLE WHICH ARE NOT VISIBLE, NOT RECORDED, OR NOT DISCLOSED IN THE TITLE COMMITMENT PROVIDED BY THE OWNER, THE PURCHASER, OR ANY AGENTS THEREOF.
2. THE UTILITIES SHOWN ARE FOR THE CLIENTS CONVENIENCE ONLY - THERE MAY BE OTHER UNDERGROUND UTILITIES NOT SHOWN HEREON. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE UNDERGROUND UTILITIES SHOWN OR NOT SHOWN. ALL DAMAGES MADE TO EXISTING UTILITIES BY THE OWNER, OR THE OWNERS AGENT, SHALL BE THE SOLE RESPONSIBILITY OF THE OWNER, OR THE OWNERS AGENT, I.E. UNDERGROUND TANKS, GAS LINES, WATER LINES, SEWER LINES, ETC.
3. ACCORDING TO THE F.E.M.A. FLOOD INSURANCE RATE MAP, COMMUNITY PANEL NUMBER 13113C0107E, EFFECTIVE 09/26/2008, FOR FAYETTE COUNTY, GEORGIA, THIS PROPERTY DOES LIE WITHIN A 100 YEAR FLOOD PLAIN AS DEFINED BY F.E.M.A.
4. BOUNDARY AND RIGHT-OF-WAY INFORMATION SHOWN HEREON IS DERIVED FROM INFORMATION PROVIDED BY FAYETTE COUNTY.
5. TOPOGRAPHIC INFORMATION SHOWN HEREON IS DERIVED FROM GIS INFORMATION PROVIDED BY FAYETTE.
6. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS LOCATED ON THE SITE AND COORDINATE ANY DISCREPANCIES WITH THE DESIGN PROFESSIONAL.
7. ALL TREES LOCATED INSIDE THE LOD ARE TO BE REMOVED.
8. ALL GOLF CART PATHS INSIDE THE LOD ARE TO BE DEMOLISHED.

FEMA STATEMENT

THIS PROPERTY IS NOT LOCATED IN A 100 YEAR FLOOD HAZARD AREA BASED ON THE FLOOD INSURANCE RATE MAP FOR THIS AREA. THE MAP NUMBER FOR THIS AREA IS 13113C0107E AND THE DATE OF SAID MAP IS SEPTEMBER 26, 2008.

IF ANY CONFLICTS, DISCREPANCIES OR OTHER UNSATISFACTORY CONDITIONS ARE DISCOVERED, EITHER ON THE CONSTRUCTION DOCUMENTS OR THE FIELD CONDITIONS, THE CONTRACTOR MUST NOTIFY THE ENGINEER IMMEDIATELY AND SHALL NOT COMMENCE OPERATION UNTIL THE CONFLICTS, DISCREPANCIES OR OTHER UNSATISFACTORY CONDITIONS ARE RESOLVED.



24 HOUR CONTACT:
BARRY BABB
TEL: (770)- 706-4800

SCALE IN FEET




200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION


NO.	REVISION REFERENCE	DATE



GSWCC CERT #78081
SHEET TITLE
**EXISTING CONDITIONS
AND DEMOLITION PLAN**

DRAWN BY TBA	CHECKED BY SMM
SCALE 1"=100'	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
DRAWING NUMBER
C-100
SHEET 2 of 37



SEE SHEET C-202

CURVE NO. = 7
 PI STA. = 254+01.93
 N = 1265968.7409
 E = 2224914.5498
 Δ = 154°20'14.5"
 D = 19°45'25.8"
 L = 1273.22
 L = 781.17
 R = 290.00

24 HOUR CONTACT:
 BARRY BABB
 TEL: (770)- 706-4800

SCALE IN FEET

CROY
 200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620
THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION OF CROY ENGINEERING, L.L.C. ANY REVISIONS TO THESE PLANS SHALL BE INDICATED BY A REVISION TABLE AND A REVISION NUMBER.

FAYETTE COUNTY SHERIFF
 VEHICLE TACTICAL TRAINING FACILITY
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

NO.	REVISION REFERENCE	DATE
02	VIEWPORT REVISION	11/22/2022
01	ACCESS ROAD REDESIGN	08/19/22

SEAL

GSWCC CERT #78081

SHEET TITLE
 SITE AND UTILITY PLAN


DRAWN BY ORG	CHECKED BY SMM
SCALE 1"=50'	ISSUE DATE 04/01/2022

PROJECT NUMBER
 1866.033
 DRAWING NUMBER
C-201
 SHEET 4 of 37

Drawing Location: P:\Marietta\1866 Fayette County\1866.033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Plan.dwg
 Plot Scale: 1"=50'
 Plot Date: 04/01/2022 9:02 AM
 Plot Size: Design.ctb, Plotted By: Chris Wade on 04/01/2022 9:02 AM

ISSUED FOR CONSTRUCTION

SEE SHEET C-201



SEE SHEET C-203

CURVE NO.= 1 PI STA.= 205+05.03 N= 1264536.5216 E= 2226116.9131 Δ= 21°58'56.0" D= 15°54'55.8" T= 69.92 L= 138.12 R= 360.00	CURVE NO.= 2 PI STA.= 209+19.42 N= 1264341.1447 E= 2226484.3024 Δ= 53°59'19.2" D= 183.38 T= 339.22 R= 360.00	CURVE NO.= 6 PI STA.= 230+79.94 N= 1263718.6770 E= 2225490.2253 Δ= 15°04'12.3" D= 15°52'17.1" T= 47.75 L= 162.00 R= 361.00	CURVE NO.= 8 PI STA.= 302+54.81 N= 1264393.5811 E= 2226236.9132 Δ= 32°00'23.2" D= 19°45'25.8" T= 83.17 L= 162.00 R= 290.00	CURVE NO.= 10 PI STA.= 408+96.69 N= 1264247.8567 E= 2225354.8354 Δ= 80°03'20.0" D= 19°45'25.8" T= 243.58 L= 405.20 R= 290.00	CURVE NO.= 11 PI STA.= 401+42.38 N= 1264566.4623 E= 2226060.6121 Δ= 52°17'58.5" D= 19°45'25.8" T= 142.38 L= 264.71 R= 290.00
--	---	--	--	--	--

24 HOUR CONTACT:
BARRY BABB
TEL: (770)- 706-4800

SCALE IN FEET

CROY
200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE
02	VIEWPORT REVISION	11/22/2022

SEAL

GSWCC CERT #78081

SHEET TITLE
SITE AND UTILITY PLAN



DRAWN BY ORG	CHECKED BY SMM
SCALE 1"=50'	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
DRAWING NUMBER
C-202
SHEET 5 of 37

Drawing Location: "F:\Marietta\1866 Fayette County\1866\033 Fayette County Sheriff Vehicle Tactical Training Track\TrackEngineering\Design\1866.033_Plan.dwg
Plot Scale: 1"=50'
Drawing Revision: #/##/##
Plot Style: Design.ctb
Plotted By: Chris Wade on 8/23/2024, 9:03 AM

CURVE NO.= 3 PI STA.= 215+84.26 N= 1263655.5145 E= 2226580.7815 Δ= 45°58'41.7" D= 6°07'39.7" T= 396.69 L= 750.33 R= 935.03	CURVE NO.= 4 PI STA.= 221+73.13 N= 1263157.3661 E= 2226191.9632 Δ= 66°12'35.5" D= 15°52'54.9" T= 235.22 L= 416.89 R= 360.76	CURVE NO.= 5 PI STA.= 225+82.88 N= 1263270.8682 E= 2225742.7717 Δ= 46°23'52.8" D= 15°54'55.8" T= 154.29 L= 291.53 R= 360.00	CURVE NO.= 9 PI STA.= 322+22.26 N= 1262441.0143 E= 2226511.5851 Δ= 158°37'46.0" D= 19°45'25.8" T= 1536.95 L= 802.90 R= 290.00
--	---	---	---

SEE SHEET C-202




200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE
02	VIEWPORT REVISION	11/22/2022







GSWCC CERT #78081
SHEET TITLE
SITE AND UTILITY PLAN

DRAWN BY ORG	CHECKED BY SMM
SCALE 1"=50'	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
DRAWING NUMBER

C-203
SHEET 6 of 37

Drawing Location: P:\Marietta\1866 Fayette County\1866.033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Plan.dwg
Plot Scale: 1"=50'
Plot Style: Design.ctb, Plotted By: Chris Wade on 8/25/2024, 9:03 AM



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620
THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION AND CONSENT OF CROY ENGINEERING, L.L.C. ANY PARTY WHO DOES SO WILL BE RESPONSIBLE TO THE APPLICABLE LAW FOR ANY AND ALL DAMAGES THAT MAY BE INCURRED.

FAYETTE COUNTY SHERIFF
 VEHICLE TACTICAL TRAINING FACILITY
 LAND LOT(S) 172
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

NO.	REVISION REFERENCE	DATE



GSWCC CERT #78081

SHEET TITLE
 ROADWAY PROFILE






DRAWN BY TBA	CHECKED BY SMM
SCALE N/A	ISSUE DATE 04/01/2022

PROJECT NUMBER
 1866.033
 DRAWING NUMBER

C-208
 SHEET 11 of 37

Drawing Location: P:\Marietta\1866 Fayette County\1866.033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Design.dwg
 Plot Scale: 1"=20' Horiz. 1"=10' Vert. Plot Style: Design.ctb. Plotted By: Chris Wade on 8/23/2024, 9:05 AM

ISSUED FOR CONSTRUCTION



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620

THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION OF CROY ENGINEERING, L.L.C. ANY PARTY WHO REPRODUCES OR COPIES THESE PLANS WITHOUT WRITTEN PERMISSION AND CONSENT OF CROY ENGINEERING, L.L.C. WILL BE HELD RESPONSIBLE FOR ANY DAMAGE TO ANY PARTY THAT MAY BE INCURRED AS A RESULT OF SUCH REPRODUCTION OR COPIING.
 Drawing: Roadwork: #/##/###, Plot Style: Design.ctb, Plotted By: Chris Wade on 8/23/2024, 9:05 AM
 Plot Scale: 1"=##'

FAYETTE COUNTY SHERIFF
 VEHICLE TACTICAL TRAINING FACILITY
 LAND LOT(S) 172
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION





NO.	REVISION REFERENCE	DATE



GSWCC CERT #78081
 SHEET TITLE
 ROADWAY PROFILE

DRAWN BY TBA	CHECKED BY SMM
SCALE N/A	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
 DRAWING NUMBER
C-209
 SHEET 12 of 37



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620
THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION OF THE ENGINEERING FIRM. ANY REVISIONS TO THESE PLANS SHALL BE MADE BY THE ENGINEER AND NOT BY ANY OTHER PERSON.

FAYETTE COUNTY SHERIFF

VEHICLE TACTICAL TRAINING FACILITY

LAND LOT(S) 172
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE



GSWCC CERT #78081

SHEET TITLE
ROADWAY PROFILE

DRAWN BY TBA	CHECKED BY SMM
SCALE N/A	ISSUE DATE 04/01/2022





PROJECT NUMBER
1866.033

DRAWING NUMBER

C-210

SHEET 13 of 37

Drawing Location: P:\Marietta\1866 Fayette County\1866\033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Design.dwg
 Plot Scale: 1"=20'




200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF
 VEHICLE TACTICAL TRAINING FACILITY
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE




GSWCC CERT #78081
 SHEET TITLE
 ROADWAY PROFILE

DRAWN BY ORG	CHECKED BY SMM
SCALE N/A	ISSUE DATE 04/01/2022


PROJECT NUMBER
1866.033
 DRAWING NUMBER
C-212
 SHEET 15 of 37

Drawing Location: P:\Marietta\1866 Fayette County\1866.033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Design.dwg



Plot Scale: 1"=40' Plot Style: Design.ctb, Plotted By: Chris Wade on 8/23/2024, 9:05 AM



INTERNAL TRACK



INTERNAL TRACK



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620
THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION AND CONSENT OF CROY ENGINEERING, LLC. YOU ARE HEREBY ADVISED THAT ANY REPRODUCTION OF THESE PLANS WITHOUT WRITTEN PERMISSION AND CONSENT OF CROY ENGINEERING, LLC, MAY BE HELD TO BE A VIOLATION OF APPLICABLE LAWS AND REGULATIONS.

FAYETTE COUNTY SHERIFF

VEHICLE TACTICAL TRAINING FACILITY

LAND LOT(S) 172
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE



GSWCC CERT #78081

SHEET TITLE
ROADWAY PROFILE


DRAWN BY ORG	CHECKED BY SMM
SCALE N/A	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033

DRAWING NUMBER
C-213
SHEET 16 of 37

Plot Scale: 1"=20' Plot Scale: 1"=10' Drawing Location: P:\Marietta\1866 Fayette County\1866.033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Design.dwg

Plot Scale: 1"=20' Plot Scale: 1"=10' Drawing Location: P:\Marietta\1866 Fayette County\1866.033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Design.dwg




SEE SHEET C-300

SEE SHEET C-302

24 HOUR CONTACT:
BARRY BABB
TEL: (770)- 706-4800

SCALE IN FEET



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620
THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION AND CONSENT OF CROY ENGINEERING, L.L.C. ANY USE THEREOF IS SUBJECT TO THE TERMS AND CONDITIONS OF THE PROFESSIONAL ENGINEERING CONTRACT.

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE
02	VIEWPORT REVISION	11/22/2022

SEAL

GSWCC CERT #78081



SHEET TITLE
GRADING AND DRAINAGE PLAN (PAGE 2 OF 3)

DRAWN BY ORG	CHECKED BY SMM
SCALE 1"=50'	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
DRAWING NUMBER
C-301
SHEET 20 of 37

Plot Scale: 1"=50' Drawing Location: P:\Marietta\1866 Fayette County\1866\033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Design.dwg

SEE SHEET C-301



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620
THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION AND CONSENT OF CROY ENGINEERING, L.L.C. ANY USE THEREOF IS AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO CROY ENGINEERING, L.L.C.

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
 LAND LOT(S) 172
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE
02	VIEWPORT REVISION	11/22/2022
01	REVISION REFERENCE	DATE




GSWCC CERT #78081
 SHEET TITLE
GRADING AND DRAINAGE PLAN (PAGE 3 OF 3)


DRAWN BY ORG	CHECKED BY SMM
SCALE 1"=50'	ISSUE DATE 04/01/2022

PROJECT NUMBER
 1866.033
 DRAWING NUMBER
C-302
 SHEET 21 of 37

Drawing Location: "F:\Marietta\1866 Fayette County\1866\033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866_033_Design.dwg Plot Scale: 1"=50' Plot Style: Design.ctb. Plotted By: Chris Walle on 8/23/2024, 9:11 AM



STORMWATER MANAGEMENT FOR THE DRIVING TRACK IS A TREATMENT TRAIN CONSISTING OF CONVEYANCE AND STORAGE BMPs TO REDUCE AND TREAT OF STORMWATER RUNOFF. RUNOFF FROM THE DRIVING TRACK WILL SHEET FLOW OVER VEGETATIVE FILTER STRIPS INTO GRASS CHANNELS ALONG THE TRACK. AT THE DOWNSTREAM POINT OF THE CHANNELS, SHALLOW INFILTRATION TRENCHES WILL BE INSTALLED BEFORE EXITING VIA STORM CULVERTS CONVEYED UNDER THE TRACK INTO THE FLOODPLAIN OF MORNING CREEK. ALSO REFER TO SHEET C-404 FOR ADDITIONAL DETAILS AND DESIGN INFORMATION.



TYPICAL INFILTRATION TRENCH CROSS-SECTION

24 HOUR CONTACT:
BARRY BABB
TEL: (770)- 706-4800

100 0 100 200 300
SCALE IN FEET



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE







GSWCC CERT #78081
SHEET TITLE
STORMWATER
MANAGEMENT SHEET

DRAWN BY TBA	CHECKED BY SMM
SCALE AS SHOWN	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
DRAWING NUMBER
C-403
SHEET 25 of 36

Plot Scale: 1" = 40' Plot Style: Design.ctb. Plotted By: Chris Wolfe on 8/25/2024, 9:15 AM
Drawing Location: P:\Marietta\1866 Fayette County\1866.033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Design.dwg



CROY

200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0820
ENGINEERING AND ARCHITECTURE

FAYETTE COUNTY SHERIFF

VEHICLE TACTICAL TRAINING FACILITY

LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO. REVISION REFERENCE DATE

SEAL

GEORGIA REGISTERED PROFESSIONAL ENGINEER
SCOTT M. MCNALLY

GSWCC CERT #78081

SHEET TITLE
CONSTRUCTION DETAILS

DRAWN BY TBA CHECKED BY SMM
SCALE N/A ISSUE DATE 04/01/2022

PROJECT NUMBER 1866.033
DRAWING NUMBER

C-500
SHEET 29 of 37

Drawing Location: 17 Marietta 1866 Fayette County 1866.033 Fayette County Sheriff Vehicle Tactical Training Track Engineering Design 1866.033 Cover, Notes & Details





TABLE NO. 1, ROUND PIPE - CONCRETE - CORRUGATED STEEL - CORRUGATED ALUMINUM
MINIMUM CLASS OF CONCRETE OR MINIMUM THICKNESS OF STEEL AND ALUMINUM

PIPE DIAMETER (INCHES)	TYPE	MINIMUM COVER (INCHES)	HEIGHT OF FILL IN FEET ABOVE TOP OF PIPE																		PIPE DIAMETER (INCHES)
			1-10	10-15	15-20	20-25	25-30	30-35	35-40	40-50	50-60	60-70	70-80	80-90							
12	CONCRETE	12	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	12	
12	STEEL	12	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	12	
12	ALUM	12	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	12	
18	CONCRETE	18	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	18	
18	STEEL	18	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	18	
18	ALUM	18	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	18	
24	CONCRETE	24	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	24	
24	STEEL	24	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	24	
24	ALUM	24	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	24	
30	CONCRETE	30	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	30	
30	STEEL	30	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	30	
30	ALUM	30	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	30	
36	CONCRETE	36	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	36	
36	STEEL	36	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	36	
36	ALUM	36	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	36	
42	CONCRETE	42	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	42	
42	STEEL	42	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	42	
42	ALUM	42	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	42	
48	CONCRETE	48	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	48	
48	STEEL	48	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	48	
48	ALUM	48	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	48	
54	CONCRETE	54	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	54	
54	STEEL	54	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	54	
54	ALUM	54	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	54	
60	CONCRETE	60	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	60	
60	STEEL	60	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	60	
60	ALUM	60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	60	
66	CONCRETE	66	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	66	
66	STEEL	66	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	66	
66	ALUM	66	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	66	
72	CONCRETE	72	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	72	
72	STEEL	72	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	72	
72	ALUM	72	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	72	
78	CONCRETE	78	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	78	
78	STEEL	78	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	78	
78	ALUM	78	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	78	
84	CONCRETE	84	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	84	
84	STEEL	84	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	84	
84	ALUM	84	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	84	
90	CONCRETE	90	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	90	
90	STEEL	90	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	90	
90	ALUM	90	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	90	
96	CONCRETE	96	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	96	
96	STEEL	96	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	96	
96	ALUM	96	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	96	
102	CONCRETE	102	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	102	
102	STEEL	102	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	102	
102	ALUM	102	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	102	
108	CONCRETE	108	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	108	
108	STEEL	108	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	108	
108	ALUM	108	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	108	
114	CONCRETE	114	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	114	
114	STEEL	114	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	114	
114	ALUM	114	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	114	
120	CONCRETE	120	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	120	
120	STEEL	120	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	0.64	120	
120	ALUM	120	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	0.60	120	

FOR CONDITIONS TO THE RIGHT OF THE HEAVY LINE, CLASS V CONCRETE PIPE IS REQUIRED. OTHERWISE, CLASS III CONCRETE PIPE IS REQUIRED. OTHERWISE, CLASS II CONCRETE PIPE IS REQUIRED. OTHERWISE, CLASS I CONCRETE PIPE IS REQUIRED. OTHERWISE, CLASS I CONCRETE PIPE IS REQUIRED.

TABLE NO. 2, CONCRETE MANHOLES

TABLE NO. 3, CONCRETE MANHOLES

TABLE NO. 4, CONCRETE MANHOLES

TABLE NO. 5, CONCRETE MANHOLES

TABLE NO. 6, CONCRETE MANHOLES

TABLE NO. 7, CONCRETE MANHOLES

TABLE NO. 8, CONCRETE MANHOLES

TABLE NO. 9, CONCRETE MANHOLES

TABLE NO. 10, CONCRETE MANHOLES

TABLE NO. 11, CONCRETE MANHOLES

TABLE NO. 12, CONCRETE MANHOLES

TABLE NO. 13, CONCRETE MANHOLES

TABLE NO. 14, CONCRETE MANHOLES

TABLE NO. 15, CONCRETE MANHOLES

TABLE NO. 16, CONCRETE MANHOLES

TABLE NO. 17, CONCRETE MANHOLES

TABLE NO. 18, CONCRETE MANHOLES

TABLE NO. 19, CONCRETE MANHOLES

TABLE NO. 20, CONCRETE MANHOLES

TABLE NO. 21, CONCRETE MANHOLES

TABLE NO. 22, CONCRETE MANHOLES

TABLE NO. 23, CONCRETE MANHOLES

TABLE NO. 24, CONCRETE MANHOLES

TABLE NO. 25, CONCRETE MANHOLES

TABLE NO. 26, CONCRETE MANHOLES

TABLE NO. 27, CONCRETE MANHOLES

TABLE NO. 28, CONCRETE MANHOLES

TABLE NO. 29, CONCRETE MANHOLES

TABLE NO. 30, CONCRETE MANHOLES

TABLE NO. 31, CONCRETE MANHOLES

TABLE NO. 32, CONCRETE MANHOLES

TABLE NO. 33, CONCRETE MANHOLES

TABLE NO. 34, CONCRETE MANHOLES


TABLE NO. 35, CON

EROSION, SEDIMENTATION, & POLLUTION CONTROL PLANS FOR CONSTRUCTION OF FAYETTE COUNTY SHERIFF VEHICLE TACTICAL TRAINING FACILITY

CITY OF FAYETTEVILLE, GEORGIA
CROY ENGINEERING PROJECT NO. 1866.033
MAY, 2022



LOCATION MAP (NTS)




FEMA MAP

FEMA STATEMENT
A PORTION OF THIS PROPERTY MAY LIE WITHIN THE 100 YEAR FLOOD HAZARD AREA BASED ON THE FLOOD INSURANCE RATE MAP FOR THIS AREA. THE MAP NUMBER FOR THIS AREA IS 13113C0107E AND THE DATE OF SAID MAP IS SEPTEMBER 26, 2008.

APPENDIX 1
THE ES&PC PLAN MUST INCLUDE AT LEAST FOUR (4) OF THE FOLLOWING BMPs FOR THOSE AREAS OF THE SITE WHICH DISCHARGE TO AN IMPAIRED STREAM SEGMENT AND FOR SITES WHICH GPS HAS APPROVED IN WRITING A REQUEST TO DISTURB 50 ACRES OR MORE AT ANY ONE TIME. The four items chosen must be appropriate for the site conditions.

Plan Page #	Included Y/N	Description
N/A	N	a. During construction activities, double the width of the 25-foot undisturbed vegetated buffer along all State waters requiring a buffer and the 50-foot undisturbed vegetated buffer along all State waters classified as "trout streams" requiring a buffer. During construction activities, EPD will not grant variances to any such buffers that are increased in width.
N/A	N	b. Increase all temporary sediment basins and retrofitted storm water management basins to provide sediment storage of at least 3600 cubic feet (134 cubic yards) per acre drained.
N/A	N	c. Use baffles in all temporary sediment basins and retrofitted storm water management basins to at least double the conventional flow path length to the outlet structure.
N/A	N	d. A large sign (minimum 4 feet x 8 feet) must be posted on site by the actual start date of construction. The sign must be visible from a public roadway. The sign must identify the following: (1) construction site, (2) the permittee(s), (3) the contact person(s) and telephone number(s), and (4) the permittee website where the Plan can be viewed must be provided on the submitted NOI. The sign must remain on site and the Plan must be available to the public at all times.
ER-200	Y	e. Use flocculants or coagulants and/or mulch to stabilize areas left disturbed for more than seven (7) calendar days in accordance with Part III, D.1. of the current NPDES Permits.
N/A	N	f. Conduct turbidity sampling after every rain event of 0.5 inch or greater within any 24-hour period, recognizing the exceptions specified in Part IV.D.6.d. of the current NPDES Permits.
N/A	N	g. Comply with the applicable end-of-pipe turbidity effluent limit, without the "BMP defenses" as provided for in C.C.G.A. 12-7-6 (a)(1).
N/A	N	h. Reduce the total planned site disturbance to less than 50% impervious surfaces (excluding any State-mandated buffer areas from such calculations). All calculations must be included on the Plan.
N/A	N	i. Limit the amount of disturbed area at any one time to no greater than 25 acres or 50% of the total planned site, whichever is less. All calculations must be included on the Plan.
N/A	N	j. Use "Dirt It" techniques available on the EPD website to model and manage construction storm water runoff (including sheet flow). All calculations must be included on the Plan.
N/A	N	k. Add appropriate organic soil amendments (e.g., compost) and conduct pre- and post-construction soil sampling to a depth of six (6) inches to document improved levels of soil carbon after final stabilization of the construction site.
ER-100-200	Y	l. Use mulch filter berms, in addition to a silt fence, on the site perimeter wherever construction storm water (including sheet flow) may be discharged. Mulch filter berms cannot be placed in waterways or areas of concentrated flow.
N/A	N	m. Use appropriate erosion control slope stabilization instead of concrete in all construction storm water ditches and storm drainages designed for a 25-year, 24-hour rainfall event.
N/A	N	n. Use flocculants or coagulants under a passive dosing method (e.g., flocculant blocks) within construction storm water ditches and storm drainages that feed into temporary sediment basins and retrofitted management basins.
N/A	N	o. Install seed for a minimum 20-foot width (in lieu of seeding) after final grade has been achieved, along the site perimeter wherever storm water (including sheet flow) may be discharged.
N/A	N	p. Conduct soil tests to identify and to implement site-specific fertilizer needs.
ER-100-300	Y	q. Certified personnel for primary permittees shall conduct inspections at least twice every seven (7) calendar days and within 24 hours of the end of the storm that is 0.5 inches rainfall or greater in accordance with Part IV.D.4.a.(3)(a) - (e), secondary permittees, Part IV.D.4.b.(3)(a) - (e), and tertiary permittees Part IV.D.4.c.(3)(a) - (e).
N/A	N	r. Apply the appropriate compost blankets (minimum depth 1 to 1.5 inches) to protect soil structures until vegetation is established during the final stabilization phase of the construction activity.
N/A	N	s. Use alternative BMPs whose performance has been documented to be superior to conventional BMPs as certified by a Design Professional (unless disapproved by EPD or the Georgia Soil and Water Conservation Commission). If using this item please refer to the Alternative BMP guidance document found at www.gaswc.org .
N/A	N	t. Limit the total planned site disturbance to less than 15% impervious surfaces (excluding any state mandated buffer areas from such calculations). All calculations must be included in the Plan.
N/A	N	u. Conduct inspections during the intermediate grading and drainage BMP phase and during the final BMP phase of the project by the design professional who prepared the Plan in accordance with Part IV.A.5 of the permit.
N/A	N	v. The Plan must include a statement that the primary permittee must retain the design professional who prepared the Plan to conduct inspections during the intermediate grading and drainage BMP phase and during the final BMP phase.
ER-300	Y	v. Install Post Construction BMPs (e.g., runoff reduction BMPs) which remove 80% TSS as outlined in the Georgia Stormwater Management Manual known as the Blue Book or an equivalent or more stringent design manual.



Map Unit Symbol	Map Unit Name	Acres in ACI	Percent of ACI
AKA	Atlatveta sandy loam, 0 to 3 percent slopes	1.0	1.6%
AmB	Appling sandy loam, 2 to 6 percent slopes	37.4	57.4%
AmC	Appling sandy loam, 6 to 10 percent slopes	21.6	33.1%
CeB	Cecil sandy loam, 2 to 6 percent slopes	4.2	6.5%
PaE	Paollet sandy loam, 10 to 25 percent slopes	0.2	0.3%
W	Water	0.7	1.1%
WH	Wehadkee soils, 0 to 2 percent slopes, frequently flooded	0.1	0.1%
Totals for Area of Interest		65.1	100.0%



24 HOUR CONTACT:
BARRY BABB
TEL: (770)- 706-4800

EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST
STAND ALONE CONSTRUCTION PROJECTS
SWDC: FAYETTE
Project Name: FAYETTE COUNTY SHERIFF VEHICLE TACTICAL TRAINING TRACK Address: 340 HOWELL RD
Local Issuing Authority: PAULING/DALAS Date on Plan: _____
Name & Email of person filling out checklist: SCOTT MCNALLY - SMCNALLY@CROYENGINEERING.COM

Plan Page #	Included Y/N	Description
ER-000	Y	1 The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in which the land-disturbing activity was permitted. (The completed Checklist must be submitted with the ES&PC Plan or the Plan will not be reviewed.)
ER-000	Y	2 Level of certification number issued by the Commission, signature and seal of the certified design professional. (Signature, seal and Level number must be on each sheet pertaining to ES&PC plan or the Plan will not be reviewed.)
N/A	N/A	3 Limit of disturbance shall be no greater than 50 acres at any one time without prior written authorization from the GAEPD District Office. If GAEPD approves the request to disturb 50 acres or more at any one time, the Plan must include at least 4 of the BMPs listed in Appendix 1 of this checklist and the GAEPD approval letter. * (A copy of the written approval by GAEPD must be attached to the plan or the Plan will not be reviewed.)
All 14	Y	4 The name and phone number of the 24-hour contact responsible for erosion, sedimentation and pollution control.
ER-001	Y	5 Provide the name, address, email address, and phone number of primary permittee.
ER-100-300	Y	6 Note total and disturbed acreages of the project or phase under construction.
ER-100-200	Y	7 Provide the GPS location of the construction exit for the site. Give the Latitude and Longitude in decimal degrees.
ER-100-300	Y	8 Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions.
ER-001	Y	9 Description of the nature of construction activity and existing site conditions.
ER-000	Y	10 Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary.
ER-001	Y	11 Identify the project receiving waters and describe all sensitive adjacent areas including streams, lakes, residential areas, wetlands, marshlands, etc. which may be affected.
ER-001	Y	12 Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on Part IV page 19 of the permit.
ER-001	Y	13 Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated on Part IV page 19 of the permit. *
ER-001	Y	14 Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days after installation." in accordance with Part IV.A.5 page 25 of the permit. *
ER-001	Y	15 Clearly note the statement that "Non-exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffers measured from the point of arested vegetation or within 25 feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary variance and permit." *
ER-001	Y	16 Provide a description of any buffer encroachments and indicate whether a buffer variance is required.
ER-001	Y	17 Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional." *
ER-001	Y	18 Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as authorized by a Section 404 permit." *
ER-001	Y	19 Clearly note statement that "The escape of sediment from the site shall be prevented by the installation of erosion and sediment control measures and practices prior to land disturbing activities." *
ER-001	Y	20 Clearly note statement that "Erosion control measures will be maintained at all times. If the implementation of the approved Plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented to control or treat the sediment source." *
ER-001	Y	21 Clearly note the statement that "Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding." *
N/A	N/A	22 Any construction activity which discharges storm water into an Impaired Stream Segment or within 1/4 mile upstream of and within the same watershed as, any portion of a Book Impaired Stream Segment must comply with Part III, C, of the permit. Include the complete Appendix 1 listing all the BMPs that will be used for those areas of the site which discharge to the Impaired Stream Segment. *
N/A	N/A	23 If a TMDL Implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in Item 22 above) at least six months prior to submittal of NOI, the ES&PC Plan must address any site-specific conditions or requirements included in the TMDL Implementation Plan. *
ER-001	Y	24 BMPs for concrete washdown of tools, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the dump truck construction site is prohibited.
ER-001	Y	25 Provide BMPs for the revegetation of petroleum spills and leaks.
ER-001	Y	26 Description of the measures that will be installed during the construction process to control pollutants in storm water that occur after construction operations have been completed. *
ER-001	Y	27 Description of practices to provide cover for building materials and building products on site. *
ER-001	Y	28 Description of the practices that will be used to reduce the pollutants in storm water discharges. *
ER-001	Y	29 Description and chart or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities, excavation activities, utility activities, temporary and final stabilization).
ER-001	Y	30 Provide complete requirements of inspections and record keeping by the primary permittee. *
ER-001	Y	31 Provide complete requirements of Sampling Frequency and Reporting of sampling results. *
ER-001	Y	32 Provide complete details for Retention of Records as per Part IV.F. of the permit. *
ER-001	Y	33 Description of analytical methods to be used to collect and analyze the samples from each location. *
ER-001	Y	34 Appendix B rationale for NTU values at all outlet sampling points where applicable. *
ER-100-300	Y	35 Define all sampling locations, perennial and intermittent streams and other water bodies into which stormwater is discharged. *
ER-100-300	Y	36 A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial sediment storage requirements and perimeter control BMPs, (2) intermediate grading and drainage BMPs, and (3) final BMPs. For construction sites where there will be no mass grading and the initial perimeter control BMPs, intermediate grading and drainage BMPs, and final BMPs are the same, the Plan may combine all of the BMP's into a single phase. *
ER-100-300	Y	37 Graphic scale and North arrow.
ER-100-300	Y	38 Existing and proposed contour lines with contour lines drawn at an interval in accordance with the following: Map Scale Contour Interval, ft 1 inch = 1000 ft 2.5 or 5 ft larger scale Rolling 2 - 8% 1 or 2 ft Steep 8% + 2.5 or 10 ft
ER-001	Y	39 Use of alternative BMPs whose performance has been documented to be equivalent to or superior to conventional BMPs as certified by a Design Professional (unless disapproved by GAEPD or the Georgia Soil and Water Conservation Commission). Please refer to the Alternative BMP Guidance Document found at www.gaswc.org .
ER-001	Y	40 Use of alternative BMP for application to the Equivalent BMP List. Please refer to Appendix A.2 of the Manual for Erosion & Sediment Control in Georgia 2016 Edition. *
ER-100-300	Y	41 Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to state waters and any additional buffers required by the Local Issuing Authority. Clearly note and delineate all areas of impact.
ER-100-300	Y	42 Delineation of on-site wetlands and all state waters located on and within 200 feet of the project site.
ER-100-300	Y	43 Delineation and acreage of contributing drainage basins on the project site.
HYDRO	HYDRO	44 Provide hydrology study and maps of drainage basins for both the pre- and post-developed conditions. *
HYDRO	HYDRO	45 An estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are completed.
ER-200	Y	46 Storm drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without erosion. Identify/delineate all storm water discharge points.
ER-001	Y	47 Soil series for the project site and their delineation.
ER-100-200	Y	48 The limits of disturbance for each phase of construction.
ER-100-200	Y	49 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, reworked detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment storage volume must be in place prior to and during all land disturbance activities until stabilization of the site has been achieved. A written justification explaining the decision to use equivalent controls when a sediment basin is not available must be included in the Plan for each common drainage location in which a sediment basin is not provided. A written justification as to why 67 cubic yards of storage is not available must also be given. Worksheets from the Manual included for structural BMPs and all calculations used by the storage design professional to obtain the required sediment when using equivalent controls. When discharging from sediment basins and impoundments, permittees are required to utilize outlet structures that will draw water from the surface, unless infeasible. If outlet structures that draw water from the surface are not feasible, a written justification explaining this decision must be included in the Plan.
ER-100-300	Y	50 Location of Best Management Practices that are consistent with and no less stringent than the Manual for Erosion and Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with legend.
ER-001	Y	51 Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia.
ER-001	Y	52 Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting dates and seeding, fertilizer, lime and mulching rates. Vegetative plans shall be site specific for appropriate time of the year that seeding will take place and for the appropriate geographic region of Georgia. * If using this checklist for a project that is less than 1 acre and not part of a common development, drawings 200 feet of a perennial stream, the checklist items would be N/A.

CROY ENGINEERING
200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30067
PHONE: (770) 971-5407 FAX: (770) 971-0820
WWW.CROYENGINEERING.COM

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE
3	EROSION APPENDIX 1	09/26/2022
2	ACCESS ROAD REDESIGN	08/19/2022
1	LDP COMMENTS	07/19/2022

NO. REVISION REFERENCE DATE

SEAL

 GSWCC CERT #78081

SHEET TITLE
EROSION CONTROL COVER SHEET

DRAWN BY ORG	CHECKED BY SMM
SCALE NONE	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033
DRAWING NUMBER
ER-000
SHEET 31 of 37

Effective January 1, 2024

Drawing Location: P:\1866.033\Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Cover_Notes.dwg
Plot Scale: 1"=400'
Plot Style: Design.ctb
Plotted By: Chris Wade on 02/20/2024, 9:05 AM

ES&PCP GENERAL NOTES

- 1. THE APPLICABLE EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN CHECKLIST IS LOCATED ON ER-000.
2. LEVEL II CERTIFICATION NUMBER ISSUED BY THE COMMISSION, SIGNATURE, AND SEAL OF THE CERTIFIED DESIGN PROFESSIONAL IS LOCATED ON ER-000.
3. LIMITS OF DISTURBANCE SHALL BE NO GREATER THAN 50 ACRES AT ANY ONE TIME WITHOUT PRIOR WRITTEN AUTHORIZATION FROM THE EPD APPROVED OFFICE...

PROJECT NARRATIVE

THE NATURE OF CONSTRUCTION ACTIVITY IS THE CONSTRUCTION OF A TACTICAL TRAINING TRACK, PIT MANEUVER AREA AND VIEWING TOWER.

THE RECEIVING WATERS FROM THIS CONSTRUCTION PLAN IS FLINT RIVER WHICH IS PART OF THE GREATER FLINT WATERSHED BASIN.

THE DESIGN-PROFESSIONAL WHO PREPARED THE ES&PCP PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMP'S WITHIN 7 DAYS AFTER INSTALLATION...

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

WASH-DOWN PLANS DESCRIBE PROCEDURES THAT PREVENT WASH DOWN WATER FROM ENTERING STREAMS AND RIVERS. NEVER DISPOSE OF WASH-DOWN WATER INTO A STORM DRAIN. ESTABLISH A WASH-DOWN WATER PIT LOCATED WITHIN THE TYPICAL LOCATION DETAILS FOR SILT FENCES...

OTHER CONTROLS
THE CONTRACTOR SHALL BE IN COMPLIANCE WITH WASTE DISPOSAL, SANITARY SEWER, OR SEPTIC TANK REGULATIONS DURING AND AFTER CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED.

PRODUCT SPECIFIC PRACTICES
CONCRETE TRUCKS - NO CONCRETE TRUCKS WILL BE ALLOWED TO WASHOUT OR DISCHARGE SURPLUS CONCRETE TO ANY DRAINAGE OR DRAINAGE OUTFALL.

WASTE DISPOSAL
LOCATE WASTE DISPOSAL AREAS AWAY FROM STREETS, OUTLETS, WATERCOURSES AND STORM DRAINS. WASTE COLLECTION AREAS, SUCH AS DUMPSTERS, ARE OFTEN BEST LOCATED NEAR CONSTRUCTION SITE ENTRANCES TO MINIMIZE TRAFFIC ON DISTURBED SOILS.

WASTE DISPOSAL
LOCATE WASTE DISPOSAL AREAS AWAY FROM STREETS, OUTLETS, WATERCOURSES AND STORM DRAINS. WASTE COLLECTION AREAS, SUCH AS DUMPSTERS, ARE OFTEN BEST LOCATED NEAR CONSTRUCTION SITE ENTRANCES TO MINIMIZE TRAFFIC ON DISTURBED SOILS.

WASTE DISPOSAL
LOCATE WASTE DISPOSAL AREAS AWAY FROM STREETS, OUTLETS, WATERCOURSES AND STORM DRAINS. WASTE COLLECTION AREAS, SUCH AS DUMPSTERS, ARE OFTEN BEST LOCATED NEAR CONSTRUCTION SITE ENTRANCES TO MINIMIZE TRAFFIC ON DISTURBED SOILS.

ANTICIPATED CONSTRUCTION ACTIVITY SCHEDULE

Table with columns for CONSTRUCTION ACTIVITY, MAY, JUNE, JULY, AUGUST, SEPTEMBER, OCTOBER, NOVEMBER, DECEMBER. Rows include INSTALL CONSTRUCTION EXIT, INITIAL SEDIMENT CONTROLS, MAINTAIN EROSION CONTROL DEVICES, CLEANING AND GRADING, etc.

ANTICIPATED CONSTRUCTION ACTIVITY SCHEDULE (REVISION DATE 08/22/2024)

Table with columns for CONSTRUCTION ACTIVITY, MAY-JUNE, JULY-AUG, SEPT-OCT, NOV-DEC, DEC-JAN, FEB-MAR, APRIL, MAY. Rows include INSTALL CONSTRUCTION EXIT, INITIAL SEDIMENT CONTROLS, MAINTAIN EROSION CONTROL DEVICES, CLEANING AND GRADING, etc.

INSPECTIONS

- 1. THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTION SITE OR THE RECORDS SHALL BE READILY AVAILABLE TO THE APPLICABLE DISTRICT OFFICE OF THE EPD...
2. THE DESIGN PROFESSIONAL'S REPORT OF THE RESULTS OF THE INSPECTION CONDUCTED IN ACCORDANCE WITH PART IV.A.5. OF THIS PERMIT...
3. THE DESIGN PROFESSIONAL'S REPORT OF THE RESULTS OF THE INSPECTION CONDUCTED IN ACCORDANCE WITH PART IV.A.5. OF THIS PERMIT...

SAMPLING FREQUENCY

- 1. THE PRIMARY PERMITTEE MUST SAMPLE IN ACCORDANCE WITH THE PLAN AT LEAST ONCE FOR EACH RAINFALL EVENT DESCRIBED BELOW...
2. HOWEVER, WHERE MANUAL AND AUTOMATIC SAMPLING ARE IMPOSSIBLE (AS DEFINED IN THIS PERMIT), OR ARE BEYOND THE PERMITTEE'S CONTROL, THE PERMITTEE SHALL TAKE SAMPLES AS SOON AS POSSIBLE...
3. SAMPLING BY THE PERMITTEE SHALL OCCUR FOR THE FOLLOWING QUALIFIED PERIODS TO COMPLETE THE NOTICE OF INTENT TO COVER BY THIS PERMIT AND ALL OTHER RECORDS REQUIRED BY THIS PERMIT SHALL BE REPRESENTATIVE OF THE MONITORED ACTIVITY AND REPRESENTATIVE OF THE WATER QUALITY OF THE RECEIVING WATER(S) AND/OR THE STORM WATER OUTFALLS USING THE FOLLOWING MINIMUM GUIDELINES...

REPORTING

- 1. THE APPLICABLE PERMITTEES ARE REQUIRED TO SUBMIT THE SAMPLING RESULTS TO THE EPD AT THE ADDRESS SHOWN IN PART I.C. BY THE FIFTEENTH DAY OF THE MONTH FOLLOWING THE REPORTING PERIOD...
2. ALL SAMPLING REPORTS SHALL INCLUDE THE FOLLOWING INFORMATION:
A. THE BRAND, MODEL, DATE, EXACT PLACE AND TIME OF SAMPLING OR MEASUREMENTS;
B. THE NAME(S) OF THE CERTIFIED PERSONNEL WHO PERFORMED THE SAMPLING AND MEASUREMENTS;
C. THE DATE(S) ANALYSES WERE PERFORMED;
D. THE TIME(S) ANALYSES WERE INITIATED;
E. THE NAME(S) OF THE CERTIFIED PERSONNEL WHO PERFORMED THE ANALYSES;
F. REFERENCES AND WRITTEN PROCEDURES, WHEN AVAILABLE, FOR THE ANALYTICAL TECHNIQUES OR METHODS USED.

RETENTION OF RECORDS

- 1. THE PRIMARY PERMITTEE SHALL RETAIN THE FOLLOWING RECORDS AT THE CONSTRUCTION SITE OR THE RECORDS SHALL BE READILY AVAILABLE TO THE APPLICABLE DISTRICT OFFICE OF THE EPD...
2. COPIES OF ALL CALIBRATION AND MAINTENANCE RECORDS AND ALL ORIGINAL STRIP CHART RECORDINGS FOR CONTINUOUS MONITORING INSTRUMENTATION, OR OTHER REPORTS REQUESTED BY THE EPD, EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS, RECORDS OF ALL DATA USED TO COMPLETE THE NOTICE OF INTENT TO COVER BY THIS PERMIT AND ALL OTHER RECORDS REQUIRED BY THIS PERMIT SHALL BE RETAINED BY THE PERMITTEE...
3. SAMPLING BY REQUEST

SAMPLING TYPE

- 1. SAMPLE CONTAINERS SHOULD BE LABELED PRIOR TO COLLECTING THE SAMPLES.
2. SAMPLES SHOULD BE WELL MIXED BEFORE TRANSFERRING TO A SECONDARY CONTAINER.
3. LARGE MOUTH, CLEAR AND RINSED GLASS OR PLASTIC JARS SHOULD BE USED FOR COLLECTING SAMPLES. THE JARS SHOULD BE CLEANED THOROUGHLY TO AVOID CONTAMINATION.
4. MANUAL, AUTOMATIC OR RISING STAGE SAMPLING MAY BE UTILIZED. SAMPLING SHOULD BE INITIATED IMMEDIATELY, BUT IN NO CASE LATER THAN 48 HOURS AFTER THE QUALIFYING EVENT. DILUTION OF SAMPLES IS NOT REQUIRED TO BE COOLED.

SAMPLING POINTS

- 1. FOR CONSTRUCTION ACTIVITIES THE PRIMARY PERMITTEE MUST SAMPLE ALL RECEIVING WATER(S), OR ALL OUTFALL(S), OR A COMBINATION OF RECEIVING WATER(S) AND OUTFALL(S). SAMPLES TAKEN FOR THE PURPOSE OF COMPLIANCE WITH THIS PERMIT SHALL BE REPRESENTATIVE OF THE MONITORED ACTIVITY AND REPRESENTATIVE OF THE WATER QUALITY OF THE RECEIVING WATER(S) AND/OR THE STORM WATER OUTFALLS USING THE FOLLOWING MINIMUM GUIDELINES:
A. THE UPSTREAM SAMPLE FOR EACH RECEIVING WATER(S) MUST BE TAKEN IMMEDIATELY UPSTREAM OF THE CONFLUENCE OF THE LAST STORMWATER DISCHARGE FROM THE PERMITTED ACTIVITY (I.E. THE DISCHARGE FARTHEST DOWNSTREAM AT THE SITE) BUT UPSTREAM OF ANY OTHER STORMWATER DISCHARGE NOT ASSOCIATED WITH THE PERMITTED ACTIVITY. WHERE APPROPRIATE, SEVERAL UPSTREAM SAMPLES FROM ACROSS THE RECEIVING WATER(S) MAY NEED TO BE TAKEN AND THE ARITHMETIC AVERAGE OF THE TURBIDITY OF THESE SAMPLES USED FOR THE UPSTREAM TURBIDITY VALUE.
B. THE DOWNSTREAM SAMPLE FOR EACH RECEIVING WATER(S) MUST BE TAKEN DOWNSTREAM OF THE CONFLUENCE OF THE LAST STORMWATER DISCHARGE FROM THE PERMITTED ACTIVITY (I.E. THE DISCHARGE FARTHEST DOWNSTREAM AT THE SITE) BUT UPSTREAM OF ANY OTHER STORMWATER DISCHARGE NOT ASSOCIATED WITH THE PERMITTED ACTIVITY. WHERE APPROPRIATE, SEVERAL DOWNSTREAM SAMPLES FROM ACROSS THE RECEIVING WATER(S) MAY NEED TO BE TAKEN AND THE ARITHMETIC AVERAGE OF THE TURBIDITY OF THESE SAMPLES USED FOR THE DOWNSTREAM TURBIDITY VALUE.
C. IDEALLY THE SAMPLES SHOULD BE TAKEN FROM THE HORIZONTAL AND VERTICAL CENTER OF THE RECEIVING WATER(S) OR THE STORM OUTLET CHANNEL(S).
D. CARE SHOULD BE TAKEN TO AVOID STIRRING THE BOTTOM SEDIMENTS IN THE RECEIVING WATER(S) OR IN THE OUTFALL STORMWATER CHANNEL.
E. THE SAMPLING CONTAINER SHOULD BE HELD SO THAT THE OPENING FACES UPSTREAM.
F. THE SAMPLES SHOULD BE KEPT FRESH FROM FLOATING DEBRIS.
G. PERMITTEES DO NOT HAVE TO SAMPLE SHEETPILE THAT FLOWS ONTO UNDISTURBED NATURAL AREAS OR AREAS STABILIZED BY THE PROJECT FOR PURPOSES OF THIS SECTION, STABILIZED SHALL BE COVERED BY UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES, AND AREAS LOCATED OUTSIDE THE WASTE DISPOSAL UNIT SHALL BE COVERED BY PERMANENT STRUCTURES AND AREAS LOCATED OUTSIDE DISPOSAL, 100% OF THE SOIL SURFACE IS UNIFORMLY COVERED IN PERMANENT VEGETATION WITH A DENSITY OF 70% OR GREATER, OR LANDSCAPED ACCORDING TO THE PLAN (UNFORMALLY COVERED WITH LANDSCAPING MATERIALS AS PLANNED LANDSCAPED AREAS), OR EQUIVALENT PERMANENT STABILIZATION MEASURES AS DEFINED IN THE MANUAL (EXCLUDING A CROP OF ANNUAL VEGETATION AND A SEEDING OF TARGET CROP PERENNIALS APPROPRIATE FOR THE REGION).

OUTFALL SAMPLING

- 1. MANUAL SAMPLING - GRAB SAMPLES WILL BE TAKEN AT THE APPROPRIATE TIME AS STATED IN PART IV.D.6.D. OF THE PERMIT. SAMPLING WILL OCCUR AT THE DESIGNATED REPRESENTATIVE OUTFALL. THE SAMPLE WILL BE TAKEN IN THE CENTER OF THE OUTFALL CHANNEL, A LARGE MOUTH, CLEAR, GLASS OR PLASTIC JAR/BOTTLE. LABELLED WITH PROJECT NUMBER AND LOCATION WILL BE USED TO COLLECT THE SAMPLE. THE SAMPLE CONTAINER WILL BE HELD SUCH THAT THE OPENING FACES UPSTREAM ONCE THE SAMPLE JAR/BOTTLE IS FULL AND CAPPED. IT WILL BE TRANSPORTED TO THE LOCATION WHERE THE TURBIDITY TESTING WILL BE CONDUCTED. SAMPLES MAY BE ANALYZED AT THE SITE WITH PROPERLY CALIBRATED PORTABLE TURBIDIMETERS. ALL TURBIDITY TESTS WILL BE CONDUCTED IMMEDIATELY BUT IN NO CASE, LATER THAN 48 HOURS AFTER THE TIME THE SAMPLE WAS OBTAINED.
2. AUTOMATIC SAMPLING - GRAB SAMPLES WILL BE TAKEN AT THE APPROPRIATE TIMES AS SPECIFIED IN PART IV.D.6.D. OF THE PERMIT. AUTOMATIC SAMPLING CAN BE ACCOMPLISHED BY USING A SAMPLING DEVICE SIMILAR TO THE 1500 MODEL 3700 OR 6700. THE PROBE FOR THE AUTOMATIC SAMPLER WILL BE PLACED IN THE CENTER OF THE CHANNEL. SAMPLES WILL REMAIN IN THE AUTOMATIC SAMPLER UNTIL THE NEXT BUSINESS DAY, WHEN THEY WILL BE COLLECTED AND TESTED.
3. TESTING - ALL TURBIDITY TESTS SHALL BE DONE IN ACCORDANCE WITH 40 CFR PART 136 (UNLESS OTHER TEST PROCEDURES HAVE BEEN APPROVED); THE GUIDANCE DOCUMENT TITLED "NOTES STORM WATER SAMPLING GUIDANCE DOCUMENT, EPA 833-B-92-001" AND GUIDANCE DOCUMENTS THAT MAY BE PREPARED BY THE EPD. TURBIDITY RESULTS WILL BE REPORTED AND REPORTED TO EPD AND THE LIA, IF APPLICABLE, IN ACCORDANCE WITH PART IV.E OF THE PERMIT.

RECEIVING WATER SAMPLING

- 1. MANUAL SAMPLING - SAMPLES WILL BE TAKEN AT THE APPROPRIATE TIME AS STATED IN PART IV.D. 5. D. OF THE PERMIT. SAMPLING WILL OCCUR AT THE DESIGNATED REPRESENTATIVE RECEIVING WATER AT THE DOWNSTREAM LOCATION FIRST. THE SAMPLE WILL BE TAKEN AS FAR DOWNSTREAM (WITHIN THE PROJECT LIMITS ONSITE) OF THE CONFLUENCE OF THE LAST STORM WATER DISCHARGE POINT AND UPSTREAM OF ANY ADDITIONAL DISCHARGES NOT ASSOCIATED WITH THE PROJECT. THE SAMPLE WILL BE TAKEN IN THE CENTER OF THE RECEIVING WATER AT A POINT WHERE MIXING OF THE RECEIVING WATERS AND THE PROJECT OUTFALL HAS OCCURRED AND PRODUCED A HOMOGENEOUS SAMPLE. ON RECEIVING WATERS WHERE ACCESS TO THE CENTER OF THE RECEIVING WATERS IS NOT PRACTICAL, SEVERAL SAMPLES FROM ACROSS THE RECEIVING WATERS WILL BE TAKEN AND THE ARITHMETIC AVERAGE OF THE TURBIDITY OF THESE SAMPLES WILL BE USED FOR THE UPSTREAM VALUE. A LARGE MOUTH, CLEAR, GLASS OR PLASTIC JAR/BOTTLE, LABELED WITH PROJECT NUMBER AND LOCATION WILL BE USED TO COLLECT THE SAMPLE. THE SAMPLE CONTAINER WILL BE HELD SUCH THAT THE OPENING FACES UPSTREAM ONCE THE SAMPLE JAR/BOTTLE IS FULL AND CAPPED. IT WILL BE TRANSPORTED TO THE LOCATION WHERE THE TURBIDITY TESTING WILL BE CONDUCTED. SAMPLES MAY BE ANALYZED AT THE SITE WITH PROPERLY CALIBRATED PORTABLE TURBIDIMETERS. ALL TURBIDITY TESTS WILL BE CONDUCTED IMMEDIATELY BUT IN NO CASE, LATER THAN 48 HOURS AFTER THE TIME THE SAMPLE WAS OBTAINED.
2. UPSTREAM SAMPLES WILL BE TAKEN AFTER DOWNSTREAM SAMPLES HAVE BEEN ACQUIRED. THE SAMPLE WILL BE TAKEN IMMEDIATELY UPSTREAM OF THE CONFLUENCE OF THE FIRST STORM WATER DISCHARGE FROM THE PROJECT (WITHIN THE PROJECT LIMITS ONSITE). THE SAMPLE WILL BE TAKEN IN THE CENTER OF THE RECEIVING WATER, ON RECEIVING WATERS WHERE ACCESS TO THE CENTER OF THE RECEIVING WATERS IS NOT PRACTICAL, SEVERAL SAMPLES FROM ACROSS THE RECEIVING WATERS WILL BE TAKEN AND THE ARITHMETIC AVERAGE OF THE TURBIDITY OF THESE SAMPLES WILL BE USED FOR THE UPSTREAM VALUE. A LARGE MOUTH, CLEAR, GLASS OR PLASTIC JAR, LABELED WITH PROJECT NUMBER AND LOCATION WILL BE USED TO COLLECT THE SAMPLE. THE SAMPLE CONTAINER WILL BE HELD SUCH THAT THE OPENING FACES UPSTREAM ONCE THE SAMPLE JAR/BOTTLE IS FULL AND CAPPED. IT WILL BE TRANSPORTED TO THE LOCATION WHERE THE TURBIDITY TESTING WILL BE CONDUCTED. SAMPLES MAY BE ANALYZED AT THE SITE WITH PROPERLY CALIBRATED PORTABLE TURBIDIMETERS. ALL TURBIDITY TESTS WILL BE CONDUCTED IMMEDIATELY BUT IN NO CASE, LATER THAN 48 HOURS AFTER THE TIME THE SAMPLE WAS OBTAINED.

SAMPLING SITE DATA FOR OUTFALLS

Table with columns: SAMPLING OUTFALL ID, TOTAL SITE AREA (AC), DRAINAGE AREA (AC), DRAINAGE AREA (SQ MI), STREAM TYPE (WARM/COLD), NTU LIMIT. Rows A, B, C.

SEE "APPENDIX B" RATIONALE FOR OUTFALL SAMPLING POINTS IN NPDES PERMIT NO. 04100001.

SEE PLAN SHEETS FOR DELINEATION OF ALL SAMPLING LOCATIONS, PERENNIAL AND INTERMITTENT STREAMS AND OTHER WATER BODIES INTO WHICH STORM WATER IS DISCHARGED.

A DESCRIPTION OF APPROPRIATE CONTROLS AND MEASURES THAT WILL BE IMPLEMENTED AT THE CONSTRUCTION SITE.

INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMP'S - DOUBLE ROW SILT FENCE WITH MULCH IN BETWEEN, MULCHING AND TEMPORARY SEEDING.

INTERMEDIATE GRADING AND DRAINAGE BMP'S - STONE CHECK DAMS, OVERSILLS, ROCK FILTER DAMS, DOUBLE ROW OF SILT FENCE WITH MULCH IN BETWEEN, COMPOST FILTER SOCK, INLET SEDIMENT TRAP, TEMPORARY SEDIMENT TRAP, STORM DRAIN OUTLET PROTECTION, PERMANENT AND TEMPORARY SEEDING AND SLOPE STABILIZATION.

FINAL BMP'S - STORM DRAIN OUTLET PROTECTION, SLOPE STABILIZATION AND PERMANENT SEEDING.

GRAPHIC SCALE AND NORTH ARROW ARE SHOWN ON ALL PLAN SHEETS.

EXISTING AND PROPOSED CONTOUR LINES ARE DRAWN ON THE PLAN SHEETS.

USE OF ALTERNATIVE BMP'S WHOSE PERFORMANCE HAS BEEN DOCUMENTED TO BE EQUIVALENT TO OR SUPERIOR TO CONVENTIONAL BMP'S AS CERTIFIED BY A DESIGN PROFESSIONAL (UNLESS DISAPPROVED BY EPD OR THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION), PLEASE REFER TO THE ALTERNATIVE BMP GUIDANCE DOCUMENT FOUND AT www.gswcc.org.

USE OF ALTERNATIVE BMP FOR APPLICATION TO THE EQUIVALENT BMP LIST. PLEASE REFER TO APPENDIX A-2 OF THE MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA 2016 EDITION.

SEE PLAN SHEETS FOR DELINEATION OF THE APPLICABLE 25-FOOT OR 50-FOOT UNDISTURBED BUFFERS ADJACENT TO STATE WATERS AND ANY ADDITIONAL BUFFERS REQUIRED BY THE LOCAL ISSUING AUTHORITY.

SEE PLAN SHEETS FOR DELINEATION OF ON-SITE WETLANDS AND ALL STATE WATERS LOCATED ON AND WITHIN 200 FEET OF THE PROJECT SITE.

SEE PLAN SHEETS FOR DELINEATION AND ACREAGE OF CONTRIBUTING DRAINAGE BASINS ON THE PROJECT SITE.

PRE- AND POST-DRAINING MAPS ARE INCLUDED IN THE HYDROLOGY STUDY.

PRE-CONSTRUCTION SITE SCS CURVE NUMBER = .61, AND THE POST-CONSTRUCTION SITE SCS CURVE NUMBER = .63.

SEE ST CHART ON PLAN SHEETS FOR STORM DRAIN PIPE VELOCITIES.

SOIL SERIES INFORMATION FOR A SUMMARY OF THE SOILS THAT ARE EXPECTED TO BE FOUND ON THE PROJECT SITE BASED ON NRCS SOILS MAPS: SEE SHEET ER-000 FOR SOIL SERIES DELINEATION AND THE TABLE BELOW FOR SOIL DESCRIPTIONS.

Table with columns: SOILS SERIES TABLE, ALTAVISTA SANDY LOAM, AKA, 0 TO 3 PERCENT SLOPES.

LIMITS OF DISTURBANCE

- 1. INITIAL PHASE: 38.29 ACRES
2. INTERMEDIATE PHASE: 38.29 ACRES
3. FINAL PHASE: 0.00 ACRES

CALCULATIONS ARE PROVIDED ON THE PLAN SHEETS.

LOCATION OF BEST MANAGEMENT PRACTICES THAT ARE CONSISTENT WITH AND NO LESS STRINGENT THAN THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA. USE UNIFORM CODING SYMBOLS FROM THE MANUAL, CHAPTER 6, WITH LEGEND.

SEE SHEET ER-200-400

SEE SHEET ER-500-501

SEE SHEET VEGETATIVE PLAN, NOTING ALL TEMPORARY AND PERMANENT VEGETATIVE PRACTICES, INCLUDING SPECIES, PLANTING DATES AND SEEDING, FERTILIZER, MULCH AND MULCHING RATES, VEGETATIVE PLAN SHALL BE SITE SPECIFIC FOR APPROPRIATE TIME OF THE YEAR THAT SEEDING WILL TAKE PLACE AND FOR THE APPROPRIATE GEOGRAPHIC REGION OF GEORGIA.

CROY logo and address: 200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413, MARIETTA, GA 30067. PHONE: (770) 971-5407, FAX: (770) 971-0820.

FAYETTE COUNTY SHERIFF VEHICLE TACTICAL TRAINING FACILITY LAND LOT(S) 172 OF THE 5TH DISTRICT, 5TH SECTION FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

Table with columns: NO., REVISION REFERENCE, DATE. Row 1: 1, LP COMMENTS, 07/19/2022.

SEAL of the State of Georgia Professional Engineer, No. 18623004, Name: BARRY BABB.


GSWCC CERT #78081 SHEET TITLE EROSION CONTROL NOTES

DRAWN BY ORG CHECKED BY SMM SCALE NONE ISSUE DATE 04/01/2022

PROJECT NUMBER 1866.033 DRAWING NUMBER ER-100

Contact 811 before you dig. SHEET 32 of 37

Vertical text on the right edge: FAYETTE COUNTY SHERIFF VEHICLE TACTICAL TRAINING FACILITY LAND LOT(S) 172 OF THE 5TH DISTRICT, 5TH SECTION FAYETTE COUNTY, GEORGIA. ISSUED FOR CONSTRUCTION. Drawing Location: C:\Users\11656\Fayette County\1866.033\Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Cover_Notes_Digital.dwg. Plot Scale: 1"=40' Plot Style: Dwg.ctb. Plotted by: Chris Wade on 08/22/2024, 9:05 AM.



EROSION CONTROL NOTES

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENTATION CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES.

EROSION AND SEDIMENT CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE. PRACTICES WILL BE CHECKED DAILY.

NO LAND DISTURBANCE, CONSTRUCTION PROCESSES, OR STORAGE OF EQUIPMENT OR MATERIALS SHALL TAKE PLACE WITHIN A DESIGNATED TREE PROTECTION AREA IN ORDER TO PREVENT DIRECT PHYSICAL ROOT DAMAGE THAT OCCURS DURING SITE CLEARING AND GRADING AND CAN CAUSE TRANSPORT OR FEEDER ROOTS TO BE CUT, TORN, OR REMOVED; INDIRECT ROOT DAMAGE CAUSED FROM GRADE CHANGES; AND TRUNK AND CROWN DAMAGE CAUSED BY DIRECT CONTACT WITH LAND CLEARING MACHINERY OR GALLING OF ADJACENT TREES.

USE OF ALTERNATIVE BMPs WHOSE PERFORMANCE HAS BEEN DOCUMENTED TO BE EQUIVALENT TO OR SUPERIOR TO CONVENTIONAL BMPs AS CERTIFIED BY A DESIGN PROFESSIONAL (UNLESS DISAPPROVED BY EPD OR THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION). PLEASE REFER TO THE ALTERNATIVE BMP GUIDANCE FOUND AT www.gaswcc.georgia.gov.

USE OF ALTERNATIVE BMP FOR APPLICATION TO THE EQUIVALENT BMP LIST. PLEASE REFER TO APPENDIX A-2 OF THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA 2016 EDITION.

INITIAL PHASE NARRATIVE:

INITIAL PHASE IS THE INSTALLATION OF PERIMETER CONTROL BMPs INCLUDING CONSTRUCTION EXIT AND DOUBLE ROW OF SILT FENCE WITH MULCH. ONCE PERIMETER CONTROLS ARE INSTALLED AND FUNCTIONING DEMOLITION AND GRADING OPERATIONS CAN COMMENCE.

STRUCTURAL BMP LEGEND

Co		CONSTRUCTION EXIT
Sd1-S DOUBLE ROW		DOUBLE ROW OF SILT FENCE WITH LOOSE MULCH IN BETWEEN
Du		DUST CONTROL ON DISTURBED AREAS
Sd4-C		TEMPORARY SEDIMENT TRAP - ROCK OUTLET
Sd2-1		EXCAVATED INLET SEDIMENT TRAP

— LOD — LIMITS OF DISTURBANCE

INITIAL PHASE DISTURBED AREA:
38.29 ACRES

VEGETATIVE BMP LEGEND

Ds1		DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)
Ds2		DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING)

24 HOUR CONTACT:
BARRY BABB
TEL: (770)-706-4800

SCALE IN FEET



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF

VEHICLE TACTICAL TRAINING FACILITY

LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE
2	ACCESS ROAD REDESIGN	08/19/2022
1	LOP COMMENTS	07/19/2022



GSWCC CERT #78081
SHEET TITLE
EROSION CONTROL PLAN - INITIAL PHASE

DRAWN BY: ORG
CHECKED BY: SMM
SCALE: 1"=100'
ISSUE DATE: 04/01/2022

PROJECT NUMBER: 1866.033
DRAWING NUMBER:
ER-200
SHEET 33 of 37

Drawing Location: P:\Marietta\1866 Fayette County\1866\033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Erosion.dwg
Plot Scale: 1"=100'
Plot Style: Design.ctb
Plotted By: Chris Walle on 8/23/2024, 9:22 AM

SEDIMENT STORAGE														
BASIN NAME	DRAINAGE AREA		DISTURBED AREA		SEDIMENT STORAGE (CY)		SILT FENCE		COMPOST FILTER SOCK		CHECK DAM		SD2-EXCAVATED	
	SF	AC	SF	AC	REQ'D SEDIMENT STORAGE	SEDIMENT STORAGE PROVIDED	LF	SEDIMENT STORAGE (CY)	LF	SEDIMENT STORAGE (CY)	EACH	SEDIMENT STORAGE (CY)	EACH	SEDIMENT STORAGE (CY)
A	237135.97	5.44	177586.60	4.08	273	1088	1173.42	704.052	0	0	0	0	1	384
B	219579.82	5.04	27451.81	0.63	42	0	0	0	0	0	0	0	0	0
C	189416.89	4.35	189416.89	4.35	291	910	0	0	1005.74	603.444	7	2.8	1	303.41
D	454096.12	10.42	259549.52	5.96	399	1403	2334.66	1400.796	0	0	5	2	0	0
E	434745.21	9.98	434745.21	9.98	669	2310	381.32	228.792	2315.75	1389.45	14	5.6	2	686.22
F	191729.35	4.40	191729.35	4.40	295	739	0	0	1223.98	734.388	11	4.4	0	0
G	496602.40	11.40	201290.51	4.62	310	1447	1169.26	701.556	0	0	12	4.8	1	740.74
TOTAL	2223305.76	51.04	1481769.89	34.02	2279	7896	5058.66	3035.196	4545.47	2727.282	49	19.6	5	2114.37

EROSION CONTROL NOTES

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENTATION CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES.

EROSION AND SEDIMENT CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE. PRACTICES WILL BE CHECKED DAILY.

NO LAND DISTURBANCE, CONSTRUCTION PROCESSES, OR STORAGE OF EQUIPMENT OR MATERIALS SHALL TAKE PLACE WITHIN A DESIGNATED TREE PROTECTION AREA IN ORDER TO PREVENT DIRECT PHYSICAL ROOT DAMAGE THAT OCCURS DURING SITE CLEARING AND GRADING AND CAN CAUSE TRANSPORT OR FEEDER ROOTS TO BE CUT, TORN, OR REMOVED; INDIRECT ROOT DAMAGE CAUSED FROM GRADE CHANGES; AND TRUNK AND CROWN DAMAGE CAUSED BY DIRECT CONTACT WITH LAND CLEARING MACHINERY OR GALLING OF ADJACENT TREES.

USE OF ALTERNATIVE BMPs WHOSE PERFORMANCE HAS BEEN DOCUMENTED TO BE EQUIVALENT TO OR SUPERIOR TO CONVENTIONAL BMPs AS CERTIFIED BY A DESIGN PROFESSIONAL (UNLESS DISAPPROVED BY EPD OR THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION). PLEASE REFER TO THE ALTERNATIVE BMP GUIDANCE FOUND AT www.goswcc.georgia.gov.

USE OF ALTERNATIVE BMP FOR APPLICATION TO THE EQUIVALENT BMP LIST. PLEASE REFER TO APPENDIX A-2 OF THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA 2016 EDITION.

INTERMEDIATE PHASE II NARRATIVE:

DURING DEMOLITION AND GRADING ACTIVITIES, INITIAL PHASE BMPs ARE TO BE MAINTAINED. SEDIMENT STORAGE WILL BE HANDLED BY DOUBLE ROW OF SILT FENCE WITH MULCH IN BETWEEN AND STONE CHECK DAMS ALONG THE SWALES. DIVERSIONS WILL BE CONSTRUCTED FOR THE ROCK DAMS, AND COMPOST FILTER SOCKS INSTALLED ON THE DESIGNATED AREAS. FILTER RINGS WILL BE CONSTRUCTED AROUND THE LABELED STORM STRUCTURES AND THE STORM INLET LOCATED WITHIN THE EXCAVATED INLET TRAP WILL REQUIRE A FILTER FABRIC WITH SUPPORTING FRAME. CHANNEL STABILIZATION IS TO BE INSTALLED IN LABELED AREAS.

DISTURBED AREA STABILIZATION SHALL BE IMPLEMENTED IN ACCORDANCE WITH THE MANUAL. CLEAN OUT ACCUMULATED SILT AND SEDIMENT STORED IN BMPs. IMPLEMENTATION AND MAINTENANCE OF ALL BMPs SHALL BE ACCORDING TO THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA. DETAILS FOR THE PROPOSED BMPs ARE INCLUDED ON SHEETS ER-400-401.

STRUCTURAL BMP LEGEND

Co		CONSTRUCTION EXIT
Cd-S		STONE CHECK DAMS
Sd1-S		DOUBLE ROW SILT FENCE-TYPE SENSITIVE WITH LOOSE MULCH IN-BETWEEN
Sd1		SINGLE ROW SILT FENCE-TYPE SENSITIVE
Sd1		COMPOST FILTER SOCK
Sd2-F		INLET SEDIMENT TRAP-FILTER FABRIC WITH SUPPORTING FRAME
SD2-1		EXCAVATED INLET SEDIMENT TRAP
St		STORM DRAIN OUTLET PROTECTION
Sd4-C		TEMPORARY SEDIMENT TRAP-ROCK OUTLET
Rt-Sg		SILT CONTROL GATE
Du		DUST CONTROL ON DISTURBED AREAS


— LOD — LIMITS OF DISTURBANCE

INTERMEDIATE PHASE DISTURBED AREA:
38.29 ACRES

VEGETATIVE BMP LEGEND

Ds1		DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)
Ds2		DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING)
Ss		SLOPE STABILIZATION

24 HOUR CONTACT:
BARRY BABB
TEL: (770)-706-4800



Sd4-C Drainage Area	Drainage Area	Dimensions	Required Sediment Storage	Provided Sediment Storage
Acre	Depth (ft)	Length (ft)	Width (ft)	ft ³
1	5.67	4	80	474

Storm Drain Outlet Protection Chart

Outlet Structure Number	Outlet Pipe Diam. "Do" (in)	Avg. Stone Diam. "d50" (in)	Length "La" (ft)	Outlet Pipe Full Flow "Q" (cfs)	Outlet Pipe Velocity "V" (fps)	Downstream Width "W2" (ft)	Stone Depth "D" (ft)	Width at the Headwall "W1" (ft)	Tailwater Condition
A1	24	0.9	24	40.31	7.87	26.0	2.025	6.0	Tw<0.5 Diameter
B0	18	0.3	9	28.54	5.49	10.5	0.675	4.5	Tw<0.5 Diameter
C0	24	0.8	20	24.57	7.01	22.0	1.8	6.0	Tw<0.5 Diameter
D0	30	1.1	21.5	31.29	8.30	24.0	2.475	7.5	Tw<0.5 Diameter
E0	36	0.8	21	50.95	15.70	24.0	1.8	9.0	Tw<0.5 Diameter
E2	30	0.5	16	40.83	9.28	18.5	1.125	7.5	Tw<0.5 Diameter
F0	24	0.3	9	24.49	6.49	11.0	0.675	6.0	Tw<0.5 Diameter
G0	30	1.2	24	44.42	9.06	26.5	2.7	7.5	Tw<0.5 Diameter
H1	18	0.3	10	11.83	5.13	11.5	0.675	4.5	Tw<0.5 Diameter

Ex. Inlet	Drainage Area	Dimensions	Required Sediment Storage	Provided Sediment Storage
	Acre	Depth (ft)	Length (ft)	Width (ft)
1	4.35	4	32	64
2	0.84	2	20	40
3	9.14	4	46	92
4	10.92	4	50	100
5	5.49	4	36	72
Totals	2059.93		55618.21	57088



CROY

200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0820

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA


NO.	REVISION REFERENCE	DATE
2	ACCESS ROAD REDESIGN	08/19/2022
1	LOP COMMENTS	07/19/2022



GSWCC CERT #78081
SHEET TITLE
EROSION CONTROL
PLAN - INTERMEDIATE
PHASE

DRAWN BY: SMM
CHECKED BY: SMM
SCALE: 1"=100'
ISSUE DATE: 04/01/2022
PROJECT NUMBER: 1866.033
DRAWING NUMBER: ER-300
SHEET 34 of 37

Drawing Location: T:\Marietta\1866\Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Erosion.dwg
Plot Scale: 1"=100'
Print Style: Design.ctb
Plotted By: Chris Wolfe on 8/25/2024, 9:25 AM



EROSION CONTROL NOTES

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENTATION CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES.

EROSION AND SEDIMENT CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE. PRACTICES WILL BE CHECKED DAILY.

NO LAND DISTURBANCE, CONSTRUCTION PROCESSES, OR STORAGE OF EQUIPMENT OR MATERIALS SHALL TAKE PLACE WITHIN A DESIGNATED TREE PROTECTION AREA IN ORDER TO PREVENT DIRECT PHYSICAL ROOT DAMAGE THAT OCCURS DURING SITE CLEARING AND GRADING AND CAN CAUSE TRANSPORT OR FEEDER ROOTS TO BE CUT, TORN, OR REMOVED; INDIRECT ROOT DAMAGE CAUSED FROM GRADE CHANGES; AND TRUNK AND CROWN DAMAGE CAUSED BY DIRECT CONTACT WITH LAND CLEARING MACHINERY OR CALLING OF ADJACENT TREES.

USE OF ALTERNATIVE BMPs WHOSE PERFORMANCE HAS BEEN DOCUMENTED TO BE EQUIVALENT TO OR SUPERIOR TO CONVENTIONAL BMPs AS CERTIFIED BY A DESIGN PROFESSIONAL (UNLESS DISAPPROVED BY EPD OR THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION). PLEASE REFER TO THE ALTERNATIVE BMP GUIDANCE FOUND AT www.gswcc.georgia.gov.


USE OF ALTERNATIVE BMP FOR APPLICATION TO THE EQUIVALENT BMP LIST. PLEASE REFER TO APPENDIX A-2 OF THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA 2016 EDITION.

FINAL PHASE NARRATIVE:


ONCE THE GRADING IS COMPLETE ACCUMULATED SEDIMENT FROM BMPs SHALL BE REMOVED FROM THE SITE AND DISPOSED OF PROPERLY IN PREPARATION OF FINAL CONSTRUCTION. CHANNEL STABILIZATION, SLOPE STABILIZATION AND PERMANENT GRASSING WILL BE INSTALLED AND MAINTAINED AS SHOWN. ONCE AREAS OF DISTURBANCE IN THIS PHASE ARE COMPLETELY STABILIZED AND ALL PERMANENT BMPs ARE IN PLACE AND FUNCTIONING PROPERLY, ALL TEMPORARY BMPs SHALL BE REMOVED.


IMPLEMENTATION AND MAINTENANCE OF ALL BMPs SHALL BE ACCORDING TO THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA. DETAILS FOR THE PROPOSED BMPs ARE INCLUDED ON SHEETS ER-500.


STRUCTURAL BMP LEGEND

St  STORM DRAIN OUTLET PROTECTION

VEGETATIVE BMP LEGEND

Ds3  DISTURBED AREA STABILIZATION (WITH PERMANENT SEEDING)

Ss  SLOPE STABILIZATION



200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
 MARIETTA, GA 30062
 PHONE: (770) 971-5407 FAX: (770) 971-0620

FAYETTE COUNTY SHERIFF

VEHICLE TACTICAL TRAINING FACILITY
 LAND LOT(S) 172
 OF THE 5TH DISTRICT, 5TH SECTION
 FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE



GSWCC CERT #78081
 SHEET TITLE
EROSION CONTROL PLAN - FINAL PHASE

DRAWN BY: SMM
 CHECKED BY: SMM
 SCALE: 1"=100'
 ISSUE DATE: 04/01/2022

PROJECT NUMBER: 1866.033
 DRAWING NUMBER:


ER-400
 SHEET 35 of 37

24 HOUR CONTACT:
 BARRY BABB
 TEL: (770)- 706-4800

100 0 100 200 300
 SCALE IN FEET


Drawing Location: "F:\Marietta\1866 Fayette County\1866\033 Fayette County Sheriff Vehicle Tactical Training Track\Engineering\Design\1866.033_Erosion.dwg
 Plot Scale: 1"=100'
 Plot Style: Design.ctb
 Plotted By: Chris Wolfe on 8/23/2024, 9:25 AM

(Co) CRUSHED STONE CONSTRUCTION EXIT




- NOTES:**
1. AVOID LOCATING ON STEEP SLOPES OR AT CURVES ON PUBLIC ROADS.
 2. REMOVE ALL VEGETATION AND OTHER UNSUITABLE MATERIAL FROM THE FOUNDATION AREA, GRADE, AND CROWN FOR POSITIVE DRAINAGE.
 3. AGGREGATE SIZE SHALL BE IN ACCORDANCE WITH NATIONAL STONE ASSOCIATION R-2 (1.5"-3.5" STONE).
 4. GRAVEL PAD SHALL HAVE A MINIMUM THICKNESS OF 6".
 5. PAD WIDTH SHALL BE EQUAL FULL WIDTH AT ALL POINTS OF VEHICULAR EGRESS, BUT NO LESS THAN 20'.
 6. A DIVERSION RIDGE SHOULD BE CONSTRUCTED WHEN GRADE TOWARD PAVED AREA IS GREATER THAN 2%.
 7. INSTALL PIPE UNDER THE ENTRANCE IF NEEDED TO MAINTAIN DRAINAGE DITCHES.
 8. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN (DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE ENTRANCE TO A SEDIMENT CONTROL DEVICE).
 9. WASHRACKS AND/OR TIRE WASHERS MAY BE REQUIRED DEPENDING ON SCALE AND CIRCUMSTANCE. IF NECESSARY, WASHRACK DESIGN MAY CONSIST OF ANY MATERIAL SUITABLE FOR TRUCK TRAFFIC THAT REMOVE MUD AND DIRT.
 10. MAINTAIN AREA IN A WAY THAT PREVENTS TRACKING AND/OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

(St) RIPRAP OUTLET PROTECTION




- NOTES:**
1. L_0 IS THE LENGTH OF THE RIPRAP APRON.
 2. $D = 1.5$ TIMES THE MAXIMUM STONE DIAMETER BUT NOT LESS THAN 6".
 3. IN A WELL-DEFINED CHANNEL, EXTEND THE APRON UP THE CHANNEL BANKS TO AN ELEVATION OF 6" ABOVE THE MAXIMUM TAILWATER DEPTH OR TO THE TOP OF THE BANK (WHICHEVER IS LESS).
 4. A FILTER BLANKET OR FILTER FABRIC SHOULD BE INSTALLED BETWEEN THE RIPRAP AND THE SOIL FOUNDATION.


(Cd-S) STONE CHECK DAM




(Sd4-C) TEMPORARY SEDIMENT TRAP




(Rd) ROCK FILTER DAM



(Sd1-S) SILT FENCE - TYPE SENSITIVE



(Sd2-F) FABRIC AND SUPPORTING FRAME FOR INLET PROTECTION



CROY

200 NORTH COBB PARKWAY, BLDG. 400, SUITE 413
MARIETTA, GA 30062
PHONE: (770) 971-5407 FAX: (770) 971-0620


THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED, CHANGED OR COPIED IN ANY FORM OR MANNER WITHOUT THE WRITTEN PERMISSION AND CONSENT OF CROY ENGINEERING, L.L.C. ANY USE OF THESE PLANS WITHOUT WRITTEN PERMISSION IS PROHIBITED.

Plot Style: Design.ctb, Plotted By: Chris Wade on 8/23/2024, 9:05 AM

FAYETTE COUNTY SHERIFF
VEHICLE TACTICAL TRAINING FACILITY
LAND LOT(S) 172
OF THE 5TH DISTRICT, 5TH SECTION
FAYETTE COUNTY, GEORGIA

ISSUED FOR CONSTRUCTION

NO.	REVISION REFERENCE	DATE



GSWCC CERT #78081

SHEET TITLE
EROSION CONTROL DETAILS

DRAWN BY TBA	CHECKED BY SMM
SCALE N/A	ISSUE DATE 04/01/2022

PROJECT NUMBER
1866.033

DRAWING NUMBER

ER-500

SHEET 36 of 37

