



Fayette COUNTY

“WHERE QUALITY
IS A LIFESTYLE”

PURCHASING DEPARTMENT
140 STONEWALL AVENUE WEST, STE 204
FAYETTEVILLE, GEORGIA 30214
PHONE: 770-305-5420
www.fayettecountyga.gov

January 10, 2017

Subject: IFB #1236-B: Resurface Three Roads – Addendum #3

Gentlemen/Ladies:

Included herein is additional information and clarification for the above referenced invitation for bids. Please consider all of this information when preparing your bid.

- 1. How will Fayette County be able to determine Prime Contractor’s percentage?**
The bidder shall list the Prime Contractor’s work percentage in the box on the revised pricing sheet.
- 2. Based on the LOG Information in the proposal the 9.5mmTP2 item is understated. Just based on the LOG there should be +/- 11,504 tons of 9.5mm TP2. If you add paving the Turn Lanes and into the Side Roads there is an additional +/- 420 tons, which will give you a total of +/- 11,924 tons not including the tons of 9.5mm TP2 that will be used in running the spreader gate out at the driveways. Based on this information Fayette County needs to increase the tons of 9.5mm TP2 for this project. Please clarify?** Fayette County would like to amend the typical section to resurface entire roadway with 1 ¼” (137.5 LBS per SY) Recycled Asphaltic Concrete 9.5mm Type II Superpave, GP 2, Only, Incl Bitum Matl & H Lime on all 3 streets. This will allow the original estimated quantity to be used on the bid sheet.
- 3. Based on the LOG Information in the proposal the Variable Depth Milling item is understated. Just based on the LOG there should be +/- 5,345 square yards of Variable Depth Milling. If you add the milling of the Side Roads there will be an additional 3,554 square yards, which will give you a total of +/- 8,899 square yards of Variable Depth Milling. Based on this information Fayette County needs to increase the square yards of Variable Depth Milling on this project. Please clarify?** The bid sheet has been revised to include this additional estimated milling for a total of 8,900 Square Yards with the intent of providing the best transition to each side road within the project limits.

Received by _____ Company _____

Note: If this addendum is not returned to the Fayette County Purchasing Department or if it is returned not signed, all responders shall still be responsible for the requirements of this addendum and the specifications or changes herein.

The opening date for this invitation for bids has not changed. **The opening date is: 3:00 p.m., Tuesday, January 17, 2017.** Bids must be received in the Purchasing Department at the address above in Suite 204 on or before the opening date and time.

Thank you for your attention to this matter.

Sincerely,



Ted L. Burgess
Director of Purchasing

TLB/tcb

Attachment

**PRICING SHEET – ADDENDUM #3
 BID #1236-B: RESURFACING THREE ROADS**

<u>ITEM NO.</u>	<u>ITEM</u>	<u>UNIT OF MEASURE</u>	<u>EST. QTY</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
150-1000	Traffic Control	LS	1		
210-0200	Grading per mile	LM	10		
402-3103	9.5mm Type 2	TON	10,642		
413-1000	Bitum Tack Coat	GL	7,377		
432-0350	Mill Asph Conc Pvmt, Variable Depth	SY	8,900		
653-1704	Themo Solid Traf Stripe 24", White	LF	227		
653-2501	Themo Solid Traf Stripe 5", White	LM	20		
653-2502	Themo Solid Traf Stripe 5", Yellow	LM	19		
653-3502	Thermo Skip Traf Stripe 5", Yellow	GLF	2,307		
653-0110	Thermo Arrow Type 1	EA	3		
654-1001	Raised Pvmt Markers, Tp 1	EA	2,806		
700-6910	Permanent Grassing	AC	12		
700-7000	Agircultural Lime	TON	18		
700-8000	Fertilizer Mixed Grade	TON	6		
700-8100	Fertilizer Nitrogen Content	LB	462		
713-3012	Wood Fiber Mulch	SY	44,756		
	TOTAL BID AMOUNT:				

Prime Contractor's Work Percentage	%
---	---

State Payment Terms _____ Days.

State Number of Days to Start Project after Notice to Proceed is issued: _____ Days.

State Number of Days to Complete Work after Start Date: _____ Days.

COMPANY NAME: _____